

| SUMMARY OF QUANTITIES | | | | TAZEWELL COUNTY 90% FEDERAL / 10% COUNTY CONSTRUCTION TYPE CODE | | |
|-----------------------|--|-------|----------------|---|--|--|
| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | HRRRP | | |
| | | | | 0021 | | |
| 20400800 | FURNISHED EXCAVATION | CU YD | 362 | 362 | | |
| 21101505 | TOPSOIL EXCAVATION AND PLACEMENT | CU YD | 485 | 485 | | |
| 20800150 | TRENCH BACKFILL | CU YD | 87 | 87 | | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 2 | 2 | | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 180 | 180 | | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 180 | 180 | | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 180 | 180 | | |
| 25100115 | MULCH, METHOD 2 | ACRE | 2 | 2 | | |
| 28000250 | TEMPORARY EROSION CONTROL SEEDING | POUND | 200 | 200 | | |
| 28000305 | TEMPORARY DITCH CHECKS | FOOT | 180 | 180 | | |
| 28000400 | PERIMETER EROSION BARRIER | FOOT | 420 | 420 | | |
| 28000500 | INLET AND PIPE PROTECTION | EACH | 3 | 3 | | |
| 31101810 | SUB-BASE GRANULAR MATERIAL, TYPE B 12" | SQ YD | 232 | 232 | | |
| 36501308 | HOT-MIX ASPHALT BASE COURSE, 6" | SQ YD | 216 | 216 | | |
| 40200800 | AGGREGATE SURFACE COURSE, TYPE B | TON | 32 | 32 | | |
| 40600215 | POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT) | TON | 3.9 | 3.9 | | |
| 40600625 | LEVELING BINDER (MACHINE METHOD) N50 | TON | 385 | 385 | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 217 | 217 | | |
| 40600990 | TEMPORARY RAMP | SQ YD | 36 | 36 | | |
| 40603510 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 412 | 412 | | |
| 44000153 | HOT-MIX ASPHALT SURFACE REMOVAL, 1" | SQ YD | 4,316 | 4,316 | | |
| 44201765 | CLASS D PATCHES TYPE II, 10 INCH | SQ YD | 47 | 47 | | |
| 48101500 | AGGREGATE SHOULDERS, TYPE B 6" | SQ YD | 27 | 27 | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 161 | 161 | | |
| 48203021 | HOT-MIX ASPHALT SHOULDERS, 6" | SQ YD | 1,370 | 1,370 | | |
| 48203029 | HOT-MIX ASPHALT SHOULDERS, 8" | SQ YD | 44 | 44 | | |
| 50104400 | CONCRETE HEADWALL REMOVAL | EACH | 2 | 2 | | |
| 50105220 | PIPE CULVERT REMOVAL | FOOT | 160 | 160 | | |
| 542A5479 | PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24" | FOOT | 108 | 108 | | |
| 542D0223 | PIPE CULVERTS, CLASS D, TYPE 1 18" | FOOT | 46 | 46 | | |
| 54214509 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 24" | EACH | 4 | 4 | | |
| 54215553 | METAL END SECTIONS 18" | EACH | 2 | 2 | | |
| 66600105 | FURNISHING AND ERECTING RIGHT OF WAY MARKERS | EACH | 4 | 4 | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | |
| * 78001110 | PAINT PAVEMENT MARKING - LINE 4" | FOOT | 5,986 | 5,986 | | |
| * 78001150 | PAINT PAVEMENT MARKING - LINE 12" | FOOT | 20 | 20 | | |
| X7010216 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 | | |
| * XX007030 | REMOVE AND RELOCATE EXSTING SIGN LIGHT | EACH | 2 | 2 | | |
| Z0013798 | CONSTRUCTION LAYOUT | L SUM | 1 | 1 | | |

* SPECIALTY ITEMS

FILE NAME =
X:\PROJECTS\
200709506\06\DEEMACK-COOPER\
PLANS-REFS\SUMMARY OF QTY.S.DGN

USER NAME =
PLOT SCALE =
PLOT DATE = 2/24/2012

DESIGNED - REW
DRAWN - KRS, DLC
CHECKED - KMC
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

TAZEWELL COUNTY - DEE-MACK ROAD AND COOPER ROAD
INTERSECTION IMPROVEMENTS
SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|----------------|----------|--------------|-----------|
| 470 | 10-00076-00 RS | TAZEWELL | 38 | 3 |

ILLINOIS FED. AID PROJECT