

ROADWAY SCHEDULE										
LOCATION	SUBBASE GRANULAR MATERIAL TYPE B	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD) N50	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE COURSE MIX "C", N50	HOT-MIX ASPHALT SHOULDERS	HOT-MIX ASPHALT SHOULDERS 6"
	6"	6"								
	31101400	35400100	40600100	40600300	40600625	40600982	40600990	40603310	48203100	48203021
	SQ YD	SQ YD	GALLON	TON	TON	SQ YD	SQ YD	TON	TON	SQ YD
FAU 7043/CH6										
STAGE 1										
LT. STA 15+25 TO LT. STA 16+82.38	70	70								
RT. STA 14+85 TO RT. STA 16+82.38	70	70	8							64
LT. STA 18+17.63 TO LT. STA 20+00	70	70								
RT. STA 18+17.63 TO RT. STA 19+75	70	70	8							72
CL. STA 15+50 TO CL. STA 16+81.88						208	24			
CL. STA 18+18.13 TO CL. STA 19+50						196	24			
STAGE 2										
LT. STA 15+25 TO LT. STA 16+82.38			10				11		12	72
RT. STA 14+85 TO RT. STA 16+82.38							11		12	
LT. STA 18+17.63 TO LT. STA 20+00			11				11		12	57
RT. STA 18+17.63 TO RT. STA 19+75							11		12	
CL. STA 15+25 TO CL. STA 16+81.88			21	1	37			33		
CL. STA 18+18.13 TO CL. STA 19+75			20	1	42			33		
TOTAL	280	280	78	2	79	404	92	66	48	265

60500050 REMOVING CATCH BASINS	
LOCATION	EACH
FAU 7043/CH6	
13 RT. STA 15+57	1
13 LT. STA 15+57	1
13 RT. STA 16+47	1
13 RT. STA 19+42	1
13 LT. STA 19+42	1
TOTAL	5

44000400 GUTTER REMOVAL	
LOCATION	FOOT
FAU 7043/CH6	
RT. STA 15+50 TO RT. STA 16+82.38	132
LT. STA 15+50 TO LT. STA 16+82.38	132
RT. STA 18+17.63 TO RT. STA 19+50	132
LT. STA 18+17.63 TO LT. STA 19+50	132
TOTAL	528

20100500 TREE REMOVAL, ACRES	
LOCATION	ACRE
FAU 7043/CH6	
LT. STA 15+50 TO LT. STA 16+80	0.02
LT. STA 18+20 TO LT. STA 20+00	0.05
TOTAL	0.07
TOTAL USE	0.10

25100630 EROSION CONTROL BLANKET	
LOCATION	SQ YD
FAU 7043/CH6	
LT. STA 15+25 TO LT. STA 16+80	246
TOTAL	246

28000400 PERIMETER EROSION BARRIER	
LOCATION	FOOT
FAU 7043/CH6	
LT. STA 15+25 TO LT. STA 16+80	165
TOTAL	165

50105220 PIPE CULVERT REMOVAL	
LOCATION	FOOT
FAU 7043/CH6	
13 RT. STA 15+57	30
13 LT. STA 15+57	30
13 LT. STA 16+47	25
13 RT. STA 19+42	30
13 LT. STA 19+42	30
TOTAL	145

GUARDRAIL SCHEDULE							
LOCATION	STEEL PLATE BEAM GUARD RAIL TYPE A 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL TYPE 6A	TRAFFIC BARRIER TERMINAL TYPE 6A (MODIFIED)	TRAFFIC BARRIER TERMINAL TYPE 1 (SPECIAL) TANGENT	GUARDRAIL MARKERS TYPE A	TERMINAL MARKER DIRECT APPLIED	GUARDRAIL REMOVAL
	63000001	63100087	X6310188	63100167	78200410	78201000	63200310
	FOOT	EACH	EACH	EACH	EACH	EACH	FOOT
FAU 7043/CH6							
RT. STA 15+92 TO RT. STA 16+81.88							90
LT. STA 16+30 TO LT. STA 16+81.88							52
RT. STA 18+18.13 TO RT. STA 18+69							51
LT. STA 18+18.13 TO LT. STA 19+08							90
RT. STA 15+25.63 TO RT. STA 16+81.88	62.5	1		1		1	
LT. STA 15+88.13 TO LT. STA 16+81.88			1	1		1	
RT. STA 18+18.13 TO RT. STA 19+11.88		1		1		1	
LT. STA 18+18.13 TO LT. STA 19+74.38	62.5	1		1		1	
RT. STA 15+25.63 TO RT. STA 19+11.88					6		
LT. STA 15+88.13 TO LT. STA 19+74.38					6		
TOTAL	125	3	1	4	12	4	283