



ROUTE	SECTION	CITY	TOTAL SHEETS	SHEET NO.
F.A.U. 8526	10-00054-00-PV	FLORA	34	2
CONTRACT NO. 95672		ILLINOIS	PROJECT M-5023(011)	



TRANSVERSE CONTRACTION JOINT SPACING SHALL BE AT 12.5 FEET

### PROPOSED TYPICAL CROSS SECTION

STA. 1+08.73 TO 27+57.06



### EXISTING TYPICAL CROSS SECTION

### GENERAL NOTES

1. THE CONTRACTOR SHALL CONTACT J.U.L.I.E. BEFORE INSTALLING ANY TRAFFIC CONTROL SIGNS.
2. EXCEPT FOR TREE REMOVAL, ALL OTHER CLEARING AND GRUBBING SHALL BE INCLUDED IN THE UNIT PRICE BID FOR EARTH EXCAVATION.
3. THE BARS SHALL BE PLACED BETWEEN THE CURB AND GUTTER AND ALL CONCRETE PAVEMENT AND CONCRETE DRIVEWAYS. SEE SHEET 3 AND 12 FOR DETAILS.
4. ALL EXISTING SIGNS REQUIRING RELOCATION SHALL BE STORED AND REINSTALLED BY THE CONTRACTOR
5. NO PAYMENT FOR OVERHAUL WILL BE MADE ON THIS SECTION

### PAVEMENT DESIGN DATA

ADT = 2075 CLASS II  
P = 2005  
SU = 60  
MU = 10  
IBR = 3.0  
T.F. = 0.50  
URBAN COLLECTOR  
PAVEMENT TYPE: P.C.C. PAVEMENT, 7" THICK  
SUBGRADE TYPE: LIME MODIFIED SUBGRADE, 14" THICK