



**TYPICAL
 ROADWAY CROSSING DETAILS**

THERMOPLASTIC LINE 6"

STA TO STA	OFFSET	COLOR	QUANTITY
604+80 TO 605+02	10' LEFT	WHITE	22 FOOT
604+80 TO 605+02	10' RIGHT	WHITE	22 FOOT
631+77 TO 631+99	10' LEFT	WHITE	22 FOOT
631+77 TO 631+99	10' RIGHT	WHITE	22 FOOT
654+77 TO 654+99	10' LEFT	WHITE	22 FOOT
654+77 TO 654+99	10' RIGHT	WHITE	22 FOOT
		TOTAL	132 FOOT

THERMOPLASTIC LINE 12"

STA TO STA	TYPE	NUMBER	COLOR	QUANTITY
604+80 TO 605+02	DIAGONAL	6 @ 10 FT.	WHITE	60 FOOT
631+77 TO 631+99	DIAGONAL	6 @ 10 FT.	WHITE	60 FOOT
654+77 TO 654+99	DIAGONAL	6 @ 10 FT.	WHITE	60 FOOT
			TOTAL	180 FOOT

SIDEWALK REMOVAL SCHEDULE

STATION TO STATION	WIDTH	QUANTITY
601+70 TO 604+69	8 FT	2392 SQ. FT.
	TOTAL	2392 SQ. FT.

PORTLAND CEMENT CONCRETE SIDEWALK 5" SCHEDULE

STATION TO STATION	WIDTH	QUANTITY
601+70 TO 604+70	10 FT.	3000 SQ. FT.
605+10 TO 605+20	10 FT.	100 SQ. FT.
631+80 TO 631+90	10 FT.	100 SQ. FT.
632+06 TO 632+16	10 FT.	100 SQ. FT.
655+20 TO 655+30	10 FT.	100 SQ. FT.
655+50 TO 655+60	10 FT.	100 SQ. FT.
	TOTAL	3500 SQ. FT.

DETECTABLE WARNINGS SCHEDULE

LOCATION	WIDTH	QUANTITY
STA 605+10 TO STA 605+12	10 FT.	20 SQ. FT.
STA 631+88 TO STA 631+90	10 FT.	20 SQ. FT.
STA 632+06 TO STA 632+08	10 FT.	20 SQ. FT.
STA 655+28 TO STA 655+30	10 FT.	20 SQ. FT.
STA 655+50 TO STA 655+52	10 FT.	20 SQ. FT.
	TOTAL	100 SQ. FT.

BOLLARDS SCHEDULE

LOCATION	OFFSET	QUANTITY
STA 605+11	CENTERLINE	1 EACH
STA 631+89	CENTERLINE	1 EACH
STA 632+07	CENTERLINE	1 EACH
STA 655+29	CENTERLINE	1 EACH
STA 655+51	CENTERLINE	1 EACH
	TOTAL	5 EACH

ROADWAY CROSSING			
SCALE: N/A	APPROVED BY: SAS	DATE: 11.10.11	DRAWN BY: C.R.S. REVISED: K.P.P.
GENERAL DACEY TRAIL			DRAWING NUMBER