

**PIPE CULVERTS CLASS D, TYPE 1 12"**

STA	O/S	LENGTH	INLET PIPE PROTECTION
605+14	A.R.	30 FOOT	1.0 EACH
631+88	A.R.	38 FOOT	1.0 EACH
632+04	A.R.	28 FOOT	1.0 EACH
651+20	A.R.	24 FOOT	1.0 EACH
654+92	A.R.	28 FOOT	1.0 EACH
	<b>TOTAL</b>	<b>148 FOOT</b>	<b>5.0 EACH</b>

**PIPE CULVERTS CLASS D, TYPE 1 15"**

STA	O/S	LENGTH	INLET PIPE PROTECTION
615+50	A.R.	40 FOOT	1.0 EACH
	<b>TOTAL</b>	<b>40 FOOT</b>	<b>1.0 EACH</b>

**PIPE CULVERTS CLASS D, TYPE 1 24"**

STA	O/S	LENGTH
634+80	LEFT	18 FOOT
	<b>TOTAL</b>	<b>18 FOOT</b>

**METAL END SECTIONS**

STA	O/S	QUANTITY	SIZE
634+00	LEFT	1.0 EACH	24"

**TEMPORARY DITCH CHECKS**

STA	O/S	LENGTH
607+50	LT	6 FT
607+50	RT	6 FT
612+50	LT	8 FT
612+50	RT	8 FT
621+00	LT	8 FT
621+00	RT	8 FT
626+00	LT	8 FT
626+00	RT	8 FT
627+00	LT	8 FT
627+00	LT	8 FT
	<b>TOTAL</b>	<b>76 FT</b>

**EARTH WORK SCHEDULE**

STA TO STA	LOCATION	EARTH EXCAVATION	EARTH EXCAVATION (ADJUSTED FOR SHRINKAGE)	EMBANKMENT	EARTH WORK BALANCE WASTE (+) OR SHORTAGE (-)
600+00 TO 658+43	MAINLINE	3861	2896	1946	(+) 950
	<b>TOTALS</b>	<b>3861</b>	<b>2896</b>	<b>1946</b>	<b>(+) 950</b>

ALL QUANTITIES IN CUBIC YARDS

**SCHEDULES**

SCALE: N/A	APPROVED BY: SAS	DRAWN BY: CRS
DATE: 2/4/12	REVISED: KPP	
GENERAL DACEY TRAIL		
DRAWING NUMBER		