

DATE	REVISION
03/08/12	UPDATE PER FAA PGL 12-2 & EB67D

SUMMARY OF QUANTITIES - BASE BID

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR101580	REFURBISH 36" BEACON	L.S.	1	
AR107812	L-807 WC-12' INTERNALLY LIT	EACH	1	
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	20,050	
AR108656	3/C #6 600V UG CABLE IN UD	L.F.	1,300	
AR108658	3/C #8 600V UG CABLE IN UD	L.F.	350	
AR109100	CONSTRUCT ELECTRICAL VAULT	L.S.	1	
AR109200	INSTALL ELECTRICAL EQUIPMENT	L.S.	1	
AR109902	REMOVE ELECTRICAL EQUIPMENT	L.S.	1	
AR110013	3" DIRECTIONAL BORE	L.F.	380	
AR110610	ELECTRICAL HANDHOLE	EACH	2	
AR125410	MITL - STAKE MOUNTED	EACH	70	
AR125415	MITL - BASE MOUNTED	EACH	9	
AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	2	
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EACH	6	
AR125505	MIRL, STAKE MOUNTED	EACH	32	
AR125510	MIRL, BASE MOUNTED	EACH	8	
AR125540	MI THRESHOLD LIGHT STAKE MTD	EACH	14	
AR125620	ABBREVIATED PAPI (L-881 SYSTEM)	EACH	1	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	47	
AR125902	REMOVE BASE MOUNTED LIGHT	EACH	9	
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	2	
AR125910	REMOVE PLASI	EACH	1	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150520	MOBILIZATION	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	691	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	1,114	
AR620900	PAVEMENT MARKING REMOVAL	S.F.	1,760	
AR800564	REMOVE REFLECTOR	EACH	40	
AR800591	UPGRADE AIRPORT ROTATING BEACON	L.S.	1	

SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE NO. 1

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AS800592	MITL LED UPGRADE	EACH	79	

SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE NO. 2

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AT800580	WEED CONTROL RING	EACH	133	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	EXISTING ELECTRICAL PLAN VAULT & TAXIWAYS
5	EXISTING ELECTRICAL PLAN STA. 5+00 TO STA. 13+10
6	EXISTING ELECTRICAL PLAN STA. 13+10 TO STA. 26+75
7	EXISTING ELECTRICAL PLAN STA. 26+75 TO STA. 46+00
8	PAVEMENT MARKING DETAILS
9	PROPOSED ELECTRICAL PLAN VAULT & TAXIWAYS
10	PROPOSED ELECTRICAL PLAN STA. 5+00 TO STA. 13+10
11	PROPOSED ELECTRICAL PLAN STA. 13+10 TO STA. 26+75
12	PROPOSED ELECTRICAL PLAN STA. 26+75 TO STA. 46+00
13	LIGHT LOCATION AND SCHEDULES
14	ELECTRICAL DETAILS SHEET 1
15	ELECTRICAL DETAILS SHEET 2
16	ELECTRICAL DETAILS SHEET 3
17	ELECTRICAL DETAILS SHEET 4
18	PROPOSED PAPI DETAILS AND NOTES RUNWAY 36
19	L-807 WIND CONE ELEVATION DETAIL
20	AIRPORT ROTATING BEACON UPGRADE DETAILS AND NOTES
21	ELECTRICAL NOTES SHEET 1
22	ELECTRICAL NOTES SHEET 2
23	ELECTRICAL LEGEND AND ABBREVIATIONS
24	EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR VAULT
25	EXISTING ELECTRICAL ONE-LINE DIAGRAM FOR SRE BUILDING
26	PROPOSED FLOOR PLAN FOR AIRPORT VAULT
27	PROPOSED AIRPORT VAULT WALL ELEVATIONS
28	PROPOSED FENCE DETAILS
29	PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR VAULT AND AIRFIELD (SHEET 1)
30	PROPOSED ELECTRICAL ONE-LINE DIAGRAM FOR VAULT AND AIRFIELD (SHEET 2)
31	AIRFIELD LIGHTING CONTROL WIRING SCHEMATIC
32	LIGHTING CONTACTOR PANEL DETAIL
33	LIGHTING CONTACTOR SCHEMATIC
34	HIGH VOLTAGE WIRING SCHEMATIC
35	PANELBOARD SCHEDULE AND DETAILS
36	LEGEND PLATE SCHEDULES
37	VAULT GROUND BUS RISER
38	GROUNDING DETAILS
39	GROUNDING NOTES

SHELBY COUNTY AIRPORT
 SHELBYVILLE, ILLINOIS
 ILL. PROJ.: 2H0-4149
 A.I.P. PROJ.: 3-17-0093-B11

Hanson Proj. No. 10A00047	Filename R-002FLP.DWG	Scale AS SHOWN	Date 02/18/12
LAYOUT	KNL	CWS	01/18/12
DRAWN	KNL	CWS	02/23/12
REVIEWED	KNL/CAH	CWS	02/23/12



© Copyright Hanson Professional Services Inc. 2012
Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2986
 Ph: (217) 788-2450 Fax: (217) 788-2903
 www.hanson-inc.com
 Offices Nationwide

CONSTRUCT VAULT,
 LIGHT TAXIWAY &
 INSTALL NAVAIDS
 SUMMARY OF QUANTITIES &
 INDEX TO SHEETS

MAR 09 2012 1:36 PM KINCAC0394
 E:\10095\10A0047\10A0047D\CAD\AIRPORT\SHEET\R-002FLP.DWG