

SCHEDULE OF QUANTITIES

SN	Facility Carried	Feature Crossed	Location	Length Total	Bridge Rdwy Width	Area to be Sealed [△]	Traffic Control Standard
0040013	BR 20 BR	KISHWAUKEE RIVER	E EDGE OF BELVIDERE	363	44	18,513	701201
0040015	POPLAR GROVE RD	US 20 BR	NE OF BELVIDERE	241.7	30	8,943	701201
0040018	IL 173	PISCASAW CREEKTRIB.	AT MCHENRY CO. LN.	90	35.4	3,816	701201
0040020	IL 173	BEAVER CREEK	2.0 MI E POPLAR GROV	130.1	40	6,115	701201
0080020	ILL 78	BN RAILROAD	2 MI N ARGO FAY RD	114.5	31.5	4,408	701201
0080028	ILL 84	PLUM RIVER	1.0 MI S JCT ILL 64	355.5	43.1	17,811	701201
0080033	ILL 40	JOHNSON CREEK	1.5 MI E OF ILL 78	73.5	32.2	2,881	701201
0080034	ARGO FAY ROAD	JOHNSON CREEK	1.9 MI E OF ILL 84	185.5	32	7,235	701201
0080036	ILL 73	STRADDLE CREEK	0.2 MI N OF LANARK	104.8	32	4,087	701201
0080037	US 52 & IL 64	STRADDLE CREEK	2.4 MI. W. LANARK	167.3	32	6,525	701201
0080038	ILL 78	SAND CREEK	N EDGE ARGO FAY RD	68.8	32.5	2,718	701201
0080039	ILL 78	N BRANCH SAND CREEK	.1 MI N ARGO FAY RD	59	32.5	2,331	701201
0080040	IL 84	BN RR & ACCESS RD	.3 MI S IL64 SAVANNA	260.9	30	9,653	701201
0080041	IL 84	SOO LINE RR/CITY ST	.1 MI S IL64 SAVANNA	264.4	30	9,783	701201
0080042	IL 78	EAST PLUM RIVER	3 MI. N. MT CARROLL	185	32	7,215	701201
0080043	IL 78	EAST JOHNSON CREEK	4 MI. S. MT CARROLL	77.5	35.5	3,294	701201

MODEL: Default
 FILE: \\mhc-pw\ulb\BID\NTEC\Illinois\gov\PWIDOT\Documents\DOT_Offices\District 2\Projects\Operations\Bridges_Section\Bridges_Deck_Sealing_Contract\2018\64M86\CADD\092-040-18-sheet-cover.dgn

USER NAME = dossed	DESIGNED - _____	REVISED - _____
	DRAWN - _____	REVISED - _____
PLOT SCALE = 100,0000' / in.	CHECKED - _____	REVISED - _____
PLOT DATE = Apr-13-2018 09:32:46 AM	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	D2 BDS 2018-2	VARIOUS	16	4
CONTRACT NO. 64M86				
ILLINOIS FED. AID PROJECT				