

FILE NAME = L:\KANE\CON\22915-01\Drawings\Sheet\Submittal\SOI\_02 - 4-12-2018.PRE #00000001.dgn

SPECIALTY ITEM	SPECIAL PROVISION	CODE NUMBER	ITEM	UNIT	FUNDING		STU		CMAA-STA	
					FED/LOCAL	TOTAL QUANTITY	75% / 25%	ROADWAY IMPROV. (0004)	80% / 20%	SAFETY IMPROV. (0021)
		40600990	TEMPORARY RAMP	SQ YD		44		44		
		40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON		4087		4087		
		40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON		1839		1839		
		42001300	PROTECTIVE COAT	SQ YD		172		172		
		44000100	PAVEMENT REMOVAL	SQ YD		1262		1262		
		44000151	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	SQ YD		8433		8433		
		44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD		78		78		
		44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT		4805		4805		
		48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD		2158		2158		
		50105220	PIPE CULVERT REMOVAL	FOOT		263		263		
	*	54260315	TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTION	FOOT		108		108		
	*	54260618	SLOPED METAL END SECTION WITH GRATE, STANDARD 542411, 18", 1:4	EACH		2		2		
	*	54261224	CONCRETE END SECTION, STANDARD 542001, 24", 1:2	EACH		1		1		
	*	54261318	CONCRETE END SECTION, STANDARD 542001, 18", 1:3	EACH		2		2		
	*	54261324	CONCRETE END SECTION, STANDARD 542001, 24", 1:3	EACH		1		1		
	*	54261418	CONCRETE END SECTION, STANDARD 542001, 18", 1:4	EACH		6		6		
	*	54261424	CONCRETE END SECTION, STANDARD 542001, 24", 1:4	EACH		2		2		
	*	54263318	CONCRETE END SECTION, STANDARD 542011, 18", 1:3	EACH		1		1		
	*	54263418	CONCRETE END SECTION, STANDARD 542011, 18", 1:4	EACH		1		1		
		542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT		186		186		
		542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT		128		128		
		542A8203	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"	FOOT		95		95		
		542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT		24		24		
		59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD		44		44		
		60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH		8		8		
		60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT		126		126		
	*	60108204	PIPE UNDERDRAINS, TYPE 2, 4"	FOOT		4449		4449		
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1-FRAME, CLOSED LID	EACH		2		2		
		60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT		14		14		
		60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT		280		280		
		60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT		36		36		
		60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT		566		566		



USER NAME = Mike Moss  
 PLOT SCALE = 2.0000 / 1" = 100'  
 PLOT DATE = 4/16/2018

DESIGNED - JMS  
 DRAWN - JMS  
 CHECKED - KDF  
 DATE - 02/14/2018

REVISED - 4/16/18  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 2 OF 6 SHEETS STA. TO STA.

F.A.H. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4066	08-00112-00-CH	KANE	93	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 63858	

