



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 5, 2018

SUBJECT: FAU 7676 (Marshall Avenue)
Section 14-00266-02-PV (Mattoon)
Coles County
Contract No. 95829
Item 186
April 27, 2018 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised page 2 of the Index to the Special Provisions.**
- 3. Revised pages 7 & 8 of the Special Provisions.**
- 4. Revised sheet 4 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Jack A. Elston, P.E.
Acting Bureau Chief
Engineer of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E.", with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.
Engineer of Project Management

24.	Conflict Manhole.....	7
25.	Non Special Waste Disposal.....	7 8
26.	Status of Utilities.....	9-10
27.	SWPPP	11-18
28.	LR107-4.....	19
29.	LR 702.....	20

STORM SEWER:

All storm sewer pipe shall be SDR-35 PVC, AWWA C-900 PVC pipe, or AWWA C-905 PVC pipe as specified in the storm sewer schedule.

SDR-35 PVC Pipe shall have bell and spigot joints and flexible elastomeric seals. The material shall conform to ASTM D 3034 for pipe sizes 4" to 15". The material shall conform to ASTM F679 for pipes sizes 18" to 48". The minimum cell classification shall be 12454.

Water main quality PVC pipe shall conform to the current edition of AWWA Standard C900 for pipe sizes 4" to 12" and AWWA standard C905 for pipes sizes 14" to 48". Pipe shall have push-on joints with elastomeric gaskets. Water Main quality pipe shall be rated at a minimum of 160 PSI and shall be DR-25.

The cost to comply with this Special Provision shall be included in the various pay items for STORM SEWERS.

CONFLICT MANHOLE:

This work shall consist of installing a special storm sewer manhole to accommodate a conflict with an existing sanitary sewer at station 30+98.6+/- Left. The manhole shall be a Type A manhole per Section 602 of the Standard Specifications, Highway Standard Drawing 602401, and the plan detail for CONFLICT MANHOLES.

This work will be measured for payment at the contract unit price each CONFLICT MANHOLE and will include all labor and material as shown in the plans.

~~**NON-SPECIAL WASTE DISPOSAL:**~~

~~The bureau of Local Roads, and/or other local public agency, is responsible for determining the need for a Preliminary Site Investigation (PSI) and/or development of any special provisions for Non-State ROW portions of the project, as appropriate.~~

~~Based on the recommendations of the preliminary environmental site assessment (PESA), if the City of Mattoon wants to pursue construction in an area of potential soil contamination, the contractor shall be responsible for hiring an environmental firm with at least five (5) documented leaking underground storage tank (LUST) cleanups or that is prequalified in hazardous waste by the department to remediate any soil contamination and monitor for worker protection if any contaminated soil or groundwater is encountered.~~

~~One site with potential soil and/or groundwater contamination was identified during the preliminary assessment. This site is located at the SW corner of 12th Street and Marshall Avenue.~~

~~The material within these identified sites shall be managed in accordance to Article 669.09. Contaminants of concern shall have sampling parameters for VOCs, PNAs, and RCRA metals.~~

~~Any waste generated as a special waste, or a waste not certified as a non-special waste from this project, should be manifested off-site using the generator number associated with Coles County.~~

~~This work shall be paid for the contract lump sum price for Special Waste Plans and Reports; and according to Article 109.04 for a qualified environmental firm to monitor the area that could possibly contain the regulated substances, analysis and disposal of waste determined to be contaminated in accordance with Section 669 of the Standard Specifications.~~