

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Summary of Quantities

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 4 of 114
Contract Number 44904

CODE NUMBER	PAY ITEM	UNIT	Y002 - 1C 100% STATE TOTAL QUANTITY	URBAN	RURAL
73801100	REMOVE & RE-ERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	7.000	3.00	4.00
44003800	MEDIAN SURFACE REMOVAL	SQ FT	128.00		128.00
60618300	CONCRETE MEDIAN SURFACE 4 INCH	SQ FT	128.00		128.00
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	25.00		25.00
82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTOCELL CONTROL, 250WATT	EACH	1.00		1.00
81600115	UNIT DUCT, 2#10XLP, 1#10 XLP GROUND 3/4" POLYETHYLENE	FOOT	550.00		550.00
84200500	REMOVE EXISTING LIGHTING UNIT, SALAVGE	EACH	1.00		1.00
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO 14 5C	FOOT	686.00		686.00
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO 14 7C	FOOT	186.00		186.00
87700180	STEEL MAST ARM ASSEMBLT AND POLE, 28 FT	EACH	1.00		1.00
87702880	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT	EACH	1.00		1.00
87800400	CONCRETE FOUNDATION, TYPE E 30 INCH DIAMETER	FOOT	23.50		23.50
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	4.00		4.00
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	647.00		647.00
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.00		1.00
X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1 FACE, 3 SECTION, BRACKET MOUNTED	EACH	1.00		1.00
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1 FACE, 3 SECTION, MAST ARM MOUNTED	EACH	2.00		2.00
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1 FACE, 5 SECTION, BRACKET MOUNTED	EACH	1.00		1.00
X0325266	FURNISH & INSTALL SIGN SUPPORT BRACKET	EACH	16.00	16.00	
X0325265	REMOVE ELECTRIC SERVICE	EACH	3.00		3.00

Rev.