

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

*Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 39 of 114
Contract Number 44904*

*District 3
Schedule of Locations for Overhead Sign Structure Replacement*

Location No.:	3-01	State I.D. No.:	3S0501039L059.6		
County:	LaSalle	Route:	I-39	M.P.:	59.6
				Direction:	SB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	108.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	342.50		
REMOVE & REINSTALL WALKWAY		FOOT	31.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
This structure is being downsized from a Type IV truss to a Type II truss.					

Location No.:	3-02	State I.D. No.:	3S0501039R057.7		
County:	LaSalle	Route:	I-39	M.P.:	57.7
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE - SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	124.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	299.00		
REMOVE & REINSTALL WALKWAY		FOOT	44.00		
OVERHEAD SIGN SUPPORT GRPOUT REPAIR		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
This structure is being downsized from a Type IV truss to a Type II truss.					

Location No.:	3-03	State I.D. No.:	3S0501039R057.2		
County:	LaSalle	Route:	I-39	M.P.:	57.2
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	124.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	299.00		
REMOVE & REINSTALL WALKWAY		FOOT	44.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
This structure is being downsized from a Type IV truss to a Type II truss.					

Location No.:	3-04	State I.D. No.:	3S0501039R058.3		
County:	LaSalle	Route:	I-39	M.P.:	58.3
				Direction:	NB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	124.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	413.25		
REMOVE & REINSTALL WALKWAY		FOOT	49.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE.		EACH	1.00		
This structure is being downsized from a Type IV truss to a Type II truss.					

Location No.:	3-05	State I.D. No.:	3S0501-39L060.3		
County:	LaSalle	Route:	I-39	M.P.:	60.3
				Direction:	SB
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A		FOOT	108.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	298.25		
REMOVE & REINSTALL WALKWAY		FOOT	52.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
OVERHEAD SIGN SUPPORT GROUT REPAIR		EACH	4.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
This structure is being downsized from a Type IV truss to a Type II truss.					