

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2006-9
Various Counties
Sheet 83 of 114
Contract Number 44904

District 7
Schedule of Locations for Truss Repair & Replacement

Location No.:	7-01	State I.D. No.:	7S051U050L014.8		
County:	Lawrence	Route:	U. S. 50	M.P.:	14.8
				Direction:	WB
Description of Work	Unit	Quantity			
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00			
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	12.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00			

Location No.:	7-02	State I.D. No.:	7C025I057R166.1		
County:	Effingham	Route:	I-57	M.P.:	166.1
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
OVERHEAD SIGN STRUCTURE CANTILEVER 2CA3-0X5-6	FOOT	30.00			
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	7.20			
REMOVE & REINSTALL SIGN PANEL	SQ FT	74.75			
REMOVE & REINSTALL WALKWAY	FOOT	17.00			
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00			
RELOCATE ELECTRIC SERVICE	EACH	1.00			
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00			
UNIT DUCT, 2#10 XLP, 1#10 XLP GROUND 3/4" POLYETHYLENE	FOOT	150.00			
This overhead sign structure is being completely replaced.					

Location No.:	7-03	State I.D. No.:	7C026U051L011.0		
County:	Fayette	Route:	U.S. 51	M.P.:	11
				Direction:	SB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
STEEL MAST ARM ASSEMBLY & POLE, 28 FOOT	EACH	1.00			
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	10.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	93.00			
MEDIAM SURFACE REMOVAL	SQ FT	128.00			
CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	128.00			
REMOVE ELECTRIC SERVICE	EACH	1.00			
This overhead sign structure is being replaced with a steel mast arm and pole assembly.					

Location No.:	7-04	State I.D. No.:	7C026U051R010.9		
County:	Fayette	Route:	U.S. 51	M.P.:	10.9
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
REMOVE ELECTRIC SERVICE	EACH	2.00			
REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1.00			
REMOVE EXISTING SIGN	SQ FT	82.00			
This overhead sign structure is being completely removed.					

Location No.:	7-05	State I.D. No.:	7C026U051R011.0		
County:	Fayette	Route:	U.S. 51	M.P.:	11
				Direction:	NB
Description of Work	Unit	Quantity			
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00			
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00			
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 30 FT.	EACH	1.00			
CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	13.50			
UNIT DUCT, 2#10 XLP, 1#10 XLP GROUND 3/4" POLYETHYLENE	FOOT	400.00			
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	686.00			
ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	186.00			
TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	4.00			
REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	647.00			
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1.00			
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1.00			
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2.00			
SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1.00			
REMOVE & REINSTALL SIGN PANEL	SQ FT	135.00			
CONDUIT IN TRENCH, 2 1/2 INCH DIAMETER PVC	FOOT	25.00			
LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTOCELL CONTROL, 250 WATT	EACH	1.00			