

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A	Y031-IF	Y030-IE		
20200100	EARTH EXCAVATION	CU YD	700	700				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	12	12				
20800150	TRENCH BACKFILL	CU YD	4.5	4.5				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1210	1210				
25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	22.5	22.5				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	22.5	22.5				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	22.5	22.5				
25100630	EROSION CONTROL BLANKET	SQ YD	1210	1210				
25200200	SUPPLEMENTAL WATERING	UNIT	15	15				
28000255	TEMPORARY EROSION CONTROL SEEDING	ACRE	0.25	0.25				
28000400	PERIMETER EROSION BARRIER	FOOT	1200	1200				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1750	1750				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	4.5	4.5				
40600300	AGGREGATE (PRIME COAT)	TON	21.5	21.5				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2.5	2.5				
40600895	CONSTRUCTING TEST STRIP	EACH	3	3				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	30	30				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	10	10				
42001300	PROTECTIVE COAT	SQ YD	70	70				
44000007	BITUMINOUS SURFACE REMOVAL, 2"	SQ YD	2900	2900				
44000008	BITUMINOUS SURFACE REMOVAL, 2-1/2"	SQ YD	3585	3585				
44000100	PAVEMENT REMOVAL	SQ YD	2515	2515				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	35	35				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	200	200				
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ FT	25		25			
44004250	PAVED SHOULDER REMOVAL	SQ YD	1155	1155				
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	72	72				
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	108	108				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	50	50				

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		1000-2A	Y031-IF	Y030-IE		
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	660	660				
550A0050	STORM SEWERS CLASS A, TYPE 1 12 INCH	FOOT	8.5	8.5				
* 55039700	STORM SEWERS TO BE CLEANED	FOOT	60	60				
55100500	STORM SEWER REMOVAL 12 INCH	FOOT	6.5	6.5				
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME & GRATE	EACH	2	2				
60263000	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	8	8				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	200	200				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
70100000	TRAFFIC CONTROL AND PROTECTION STANDARD 701401	L SUM	1	1				
70100420	TRAFFIC CONTROL AND PROTECTION STANDARD 701411	EACH	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	735	735				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	475	475				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4640	4640				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	6700	6700				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2655	2655				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1410	1410				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	100	100				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	54	54				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7325	7325				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	475	475				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4640	4640				

* SPECIALITY ITEMS
* NON-PARTICIPATING ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 3/14/2006