

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
342	530 N-2	COOK	53	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

CONTRACT NO.: 60A61

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A	Y031-IF	Y030-IE		
*78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1120	1120				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2655	2655				
*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1410	1410				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	100	100				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	54	54				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	400	400				
*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	306	306				
*80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	5			5		
*81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	287		287			
*81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	120		120			
*81400200	HEAVY-DUTY HANDHOLE	EACH	2		2			
*81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1107		287	820		
*83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	40			40		
*84200705	REMOVAL OF POLE FOUNDATION PARTIAL	EACH	4			4		
*84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	4			4		
*85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	480		480			
*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1786		1786			
*87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1		1			
*87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15		15			
87900200	DRILL EXISTING HANDHOLE	EACH	1		1			
*88000170	SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2		2			
*88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	2		2			
*88500100	INDUCTIVE LOOP DETECTOR	EACH	4		4			

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000-2A	Y031-IF	Y030-IE		
*88600100	DETECTOR LOOP, TYPE I	FOOT	180		180			
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1		1			
89502375	REMOVAL EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1			
89502380	REMOVAL EXISTING HANDHOLE	EACH	2		2			
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1		1			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
*X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	1				1	
X0324387	LUMINAIRE SAFETY CABLE ASSEMBLY	EACH	4				4	
X3550900	BITUMINOUS BASE COURSE SUPERPAVE, 12"	SQ YD	1750	1750				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1225	1225				
X0325300	BITUMINOUS CONCRETE BINDER COURSE SUPERPAVE IL-19, N70, 11-1/2"	SQ YD	2515	2515				
X4067100	POLYMERIZED LEVELING BINDER (MM) SUPERPAVE IL-4.75, N50, 1"	TON	370	370				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	2	2				
Z0001050	AGGREGATE SUBGRADE, 12"	SQ YD	2515	2515				
*Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	2	2				
*X0325254	UNIT DUCT WITH 3-1/C * 1 & 1/C * 1 GROUND, 600V (EPR-TYPE RHW), 2" DIA SCHEDULE 40 POLYETHYLENE	FOOT	1300				1300	
*X0325255	DOUBLE HANDHOLE HEAVY DUTY	EACH	1				1	
81019100	CONDUIT PUSHED, 6" DIA., GALVANIZED STEEL	FOOT	75				75	
81018800	CONDUIT PUSHED 3 1/2" DIA., GALVANIZED STEEL	FOOT	110				110	

\* SPECIALITY ITEMS  
 \* NON-PARTICIPATING ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES

REV.

PLOT DATE: 3/14/2006

3/14/2006 10:00:00 AM