

EARTHWORK SCHEDULE

LOCATION DESCRIPTION	FROM		TO		EARTH EXCAVATION (CU YD)	EMBANKMENT (CU YD)	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL (CU YD)
	ALIGNMENT	STATION	ALIGNMENT	STATION			
79TH TO 75TH	SB I-94	1313+00	SB I-94	1339+00	18260	190	855
75TH TO 71ST	SB I-94	1339+50	SB I-94	1363+50	22545	35	1155
12" PGES - SEE SEPARATE SCHEDULE					944		
TOTAL					41749	225	2010

POROUS GRANULAR EMBANKMENT, SUBGRADE

ALIGNMENT	DESCRIPTION	STATION		LENGTH (FOOT)	WIDTH (FOOT)	DEPTH (INCH)	VOLUME (CU YD)
		FROM	TO				
SB I-94	MAINLINE DAN RYAN	1336+50	1339+50	300	85	12	944
TOTAL (CU YD)							944

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. 94 (DAN RYAN EXPRESSWAY)

SCHEDULE OF QUANTITIES
EARTHWORK QUANTITIES - SHEET 1

SCALE: NONE
DATE: MARCH 1, 2006
DRAWN BY: MPG
CHECKED BY: JPM