

62746

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90		COOK	81	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
--- (1012, 1214, 1415, & 1517) RS-3				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ROADWAY 100% STATE 1000				
X0324085	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	176	176				
40600300	AGGREGATE (PRIME COAT)	TON	880	880				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	132	132				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	617	617				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	67	67				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	543	543				
42001300	PROTECTIVE COAT	SQ YD	3417	3417				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	111302	111302				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	56503	56503				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	3231	3231				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	10250	10250				
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	210	210				
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	48	48				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	2684	2684				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	33	33				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	256	256				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	122500	122500				
55039700	STORM SEWERS TO BE CLEANED	FOOT	12000	12000				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	16	16				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	8	8				
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	13	13				
63200310	GUARDRAIL REMOVAL	FOOT	650	650				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12				
67100100	MOBILIZATION	L SUM	1	1				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	110	110				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN ROADWAY 100% STATE 1000				
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	131871	131871				
• 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	41418	41418				
• 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6629	6629				
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	158	158				
• 78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	31902	31902				
• 78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	466	466				
• 78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	220	220				
• 78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	263742	263742				
• 78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	63804	63804				
• 78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	82836	82836				
• 78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	13258	13258				
• 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	316	316				
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	3066	3066				
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	13	13				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3066	3066				
• 81016400	CONDUIT IN TRENCH, 1 1/4" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	100	100				
• 81016600	CONDUIT IN TRENCH, 2" DIA., HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	100	100				
• 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100	100				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1920	1920				
• X0322300	ELECTRIC CABLE IN CONDUIT NO. 18 4/C, TWISTED, SHIELDED	FOOT	600	600				
X0322729	MATERIAL TRANSFER DEVICE	TON	67252	67252				
64200105	SHOULDER RUMBLE STRIP	FOOT	88300	88300				
X4066680	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	30495	30495				

• SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
KENNEDY EXPRESSWAY

Rev.

PLOT DATE: 2/9/2006

2/9/2006