



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2006

SUBJECT: FAP Route 330
Section (102 & 102X)LS
Cook County
Contract No. 62969
Item No.156, 4/28/06 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 1 & 3 of the Schedule of Prices
2. Revised pages i of the Table of Contents to the Special Provisions
3. Revised pages 1, 2, 4 & 5 of the Special Provisions
4. Revised sheets 2, 3, 4, 8 & 9 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine
Engineer of Design
and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; Estimates; Design & Environment File

dp

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62969

State Job # - C-91-227-05
 PPS NBR - 1-77016-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (102 & 102X) LS

Project Number

Route
 FAP 330

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2C007G3	T-AMELAN CAN CG 3G	EACH	140.000				
* A2C023G3	T-CARYA OVATA CG 3G	EACH	80.000				
A2C026G3	T-CELTIS OCCID CG 3G	EACH	70.000				
A2C033G3	T-QUERCUS COCCI CG 3G	EACH	40.000				
A2C035G3	T-JUGLANS NIGRA CG 3G	EACH	70.000				
* A2C049G3	T-QUERC ALBA CG 3G	EACH	245.000				
* A2C053G3	T-QUERCUS IMBRI CG 3G	EACH	80.000				
* A2C056G3	T-QUERC MACR CG 3G	EACH	310.000				
* A2C061G3	T-QUERC RUBRA CG 3G	EACH	165.000				
A2002516	T-CARP CAROL 2	EACH	3.000				
A2006600	T-QUERCUS COCCI 1-3/4	EACH	14.000				
A2006712	T-QUERCUS MACR 1-1/2	EACH	14.000				
A2007114	T-QUERCUS RUBRA 1-3/4	EACH	14.000				
B2000562	T-AMELAN CAN SF 4'	EACH	50.000				
B2001164	T-CERCIS CAN CL 5'	EACH	8.000				
* REVISED : APRIL 12, 2006							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62969

State Job # - C-91-227-05
 PPS NBR - 1-77016-0000
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - (102 & 102X) LS

Project Number

Route
 FAP 330

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* 25200200	SUPPLE WATERING	UNIT	120.000				
67100100	MOBILIZATION	L SUM	1.000				
* 67000400	ENG FIELD OFFICE A	CAL MO	9.000				
* REVISED : APRIL 12, 2006							

TABLE OF CONTENTS

LOCATION OF IMPROVEMENT 1
DESCRIPTION OF IMPROVEMENT 1
LANDSCAPE CONSTRUCTION WORK AND LANDSCAPE ESTABLISHMENT WORK..... 1
START DATE..... 1
COMPLETION DATE FOR PHASE ONE2
COMPLETION DATE FOR PHASE TWO2
COMPLETION DATE FOR PHASE THREE.....2
FAILURE TO COMPLETE LANDSCAPE CONSTRUCTION AND LANDSCAPE ESTABLISHMENT WORK.....2
PLANTING WOODY PLANTS (CORRIDOR)3
PLANTING WOODY PLANTS (TREE MITIGATION)4
MOWING6
RESTORATION OF DISTURBED AREAS7
SUPPLEMENTAL WATERING7
GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING8
WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE 11
TRAFFIC CONTROL PLAN..... 12
TRAFFIC CONTROL DEFICIENCY DEDUCTION (BDE) 12
PAYROLLS AND PAYROLL RECORDS (BDE) 13
PAYMENTS TO SUBCONTRACTORS (BDE) 14
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... 15
PARTIAL PAYMENTS (BDE) 17
PERSONAL PROTECTIVE EQUIPMENT (BDE) 17
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 18
FLAGGER VESTS (BDE) 18

Revised 4/13/06

STATE OF ILLINOIS

SPECIAL PROVISIONS

The following Special Provisions supplement the "Standard Specifications for Road and Bridge Construction," adopted January 1, 2002, the latest edition of the "Manual on Uniform Traffic Control Devices for Streets and Highways," and the "Manual of Test Procedures for Materials" in effect on the date of invitation for bids, and the Supplemental Specifications and Recurring Special Provisions indicated on the Check Sheet included herein which apply to and govern the construction of ROUTE 330, SECTION: (102 & 102 X) LS, COUNTY: COOK and in case of conflict with any part or parts of said Specifications, the said Special Provisions shall take precedence and shall govern.

CONTRACT: 62969

LOCATION OF IMPROVEMENT

This improvement consists of two locations. The first location, herein referred to as the "Corridor", includes work both within and outside State right-of-way. It begins on US 12/20/45 (LaGrange Road) from North of Cal Sag Channel to IL 171 (Archer Avenue) and extends into Unincorporated Cook County and the Village of Willow Springs. The second location, herein referred to as "Tree Mitigation", includes work outside State right-of-way only and includes work in the Corridor in addition to the primary site, which lies adjacent to the right-of-way of US 45 from 175th Street to 171st Street in Forest Preserve District of Cook County holdings in Orland Township.

DESCRIPTION OF IMPROVEMENT

This is a landscaping and forest management project developed mutually with the Forest Preserve District of Cook County and the work to be performed under this contract consists of tree and shrub planting, weed spraying and reforestation.

LANDSCAPE CONSTRUCTION WORK AND LANDSCAPE ESTABLISHMENT WORK

The Contractor shall complete each Phase of the work in accordance with the CALENDAR OF CONSTRUCTION AND ESTABLISHMENT WORK specified in the plans.

START DATE
August 1, 2006

Revised 4/13/06

COMPLETION DATE FOR PHASE ONE

The Contractor shall schedule his/her operations in order to complete all Phase I work on or before September 15, 2006.

COMPLETION DATE FOR PHASE TWO

The Contractor shall schedule his/her operations in order to complete all Phase II work on or before May 31, 2007.

COMPLETION DATE FOR PHASE THREE

The Contractor shall schedule his/her operations in order to complete all Phase III work on or before May 31, 2008.

FAILURE TO COMPLETE LANDSCAPE CONSTRUCTION AND LANDSCAPE ESTABLISHMENT WORK

Should the Contractor fail to complete the Phase I work on or before the completion date stipulated in the contract, or within such extended time as many have been allowed, the Contractor shall be liable to the Department in the amount of \$375, not as a penalty but as liquidated damages, for each calendar day or portion thereof, of overrun in the Phase I time or such extended time as may have been allowed.

Should the Contractor fail to complete the Phase II work on or before the completion date stipulated in the contract, or within such extended time as many have been allowed, the Contractor shall be liable to the Department in the amount of \$550, not as a penalty but as liquidated damages, for each calendar day or portion thereof, of overrun in the Phase II time or such extended time as may have been allowed.

Should the Contractor fail to complete the Phase III work on or before the completion date stipulated in the contract, or within such extended time as many have been allowed, the Contractor shall be liable to the Department in the amount of \$300, not as a penalty but as liquidated damages, for each calendar day or portion thereof, of overrun in the Phase I time or such extended time as may have been allowed.

A calendar day is every day and starts at 12:00 midnight and ends at the following 12:00 midnight, twenty-four hours later.

Revised 4/13/06

Add the following to Article 253.13 Bracing:

Trees required to be braced shall be braced within 24 hours of planting.

Delete sub-paragraph (a) of Article 253.15 Plant Care and substitute the following:

Water trees, shrubs, and vines within the first 24 hours of initial planting, and not less than **twice** per month during the period of establishment. The Engineer may direct the Contractor to adjust the watering rate and frequency depending upon the weather conditions.

The water shall be applied to individual plants in such a manner that the plant hole shall be saturated without allowing the water to overflow beyond the earthen saucer. Watering of plants in beds shall be applied in such a manner that all plant holes are uniformly saturated without allowing the water to flow beyond the periphery of the bed. The plants to be watered and the method of application will be approved by the Engineer. The Contractor will not be relieved in any way from the responsibility for unsatisfactory plants due to the amount of watering.

Delete Article 253.17 and substitute the following:

Basis of Payment. This work will be paid for 75% of the contract unit price each for several kinds and sizes of trees, shrubs and vines found to be in a live and healthy condition by May 31st, as specified in Article 253.14. The remaining 25% of the contract unit price each will be paid for after the successful completion of all required replacement plantings and clean up work and receipt of the "Final Acceptance of Landscape Work" memorandum from the Bureau of Maintenance. The unit price shall include the cost of all material, equipment, labor, plant care, disposal and incidental required to complete the work as specified herein and to the satisfaction of the Engineer. The placement of Pre-emergent Herbicide shall be paid for at the contract unit price for WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE.

PLANTING WOODY PLANTS (TREE MITIGATION)

This work shall consist of planting woody plants in the Tree Mitigation Sites as specified in Section 253 of the Standard Specifications with the following revisions:

Article 253.03 Oaks (Quercus Spp.) in containers are not limited to spring planting

Add the following paragraph to Article 253.10:

When nitrogen fertilizer is specified, it shall be applied at the rate of 45 g (0.1 lb) of nutrients per 1.9 sq m (20 sq ft) within 48 hours after planting, prior to placing mulch.

Delete Article 253.11 and substitute the following:

Within 48 hours after planting, mulch shall be placed around all plants in the entire mulched bed or saucer area specified to a depth of 4 inches (100 mm). No weed barrier fabric will be required for tree and shrub planting. Pre-emergent Herbicide will be used instead of weed barrier fabric. The Pre-emergent Herbicide shall be applied prior to mulching. See specification for Weed Control, Pre-Emergent Granular Herbicide. Mulch shall not be in contact with the base of the trunk.

Revised 4/13/06

Delete the second and third sentence of paragraph 1 of Article 253.14 and substitute the following:

Plant material in the Tree Mitigation sites must undergo a 30 day period of establishment. To qualify for inspection, the Contractor must receive written certification from the Engineer stating that all specified plant material for the Tree Mitigation sites was in place and in a live healthy condition on or before **September 15** of the year of inspection.

Delete sub-paragraph (a) of Article 253.15 Plant Care and substitute the following:

Water trees, shrubs, and vines within the first 24 hours of initial planting, and not less than **twice** during the period of establishment. The Engineer may direct the Contractor to adjust the watering rate and frequency depending upon the weather conditions.

The water shall be applied to individual plants in such a manner that the plant hole shall be saturated without allowing the water to overflow beyond the earthen saucer. Watering of plants in beds shall be applied in such a manner that all plant holes are uniformly saturated without allowing the water to flow beyond the periphery of the bed. The plants to be watered and the method of application will be approved by the Engineer. The Contractor will not be relieved in any way from the responsibility for unsatisfactory plants due to the amount of watering.

Delete the second sentence of sub-paragraph (b) of Article 253.15 Plant Care and substitute the following:

This weeding shall be performed not less than twice during the period of establishment.

Add the following to Article 253.16 Method of Measurement:

Trees and shrubs will be measured in place as individual plants of the type specified. Measurement for payment of this work will not be performed until at the end of the 30 day establishment period. Only plants that are in place and acceptable at the time of measurement will be measured for payment except that if fewer than 25 percent of the plants are acceptable, a quantity equal to 25 percent of the number of plants originally planted will be considered measured for payment. Fertilizer will be measured by weight in kilograms (pounds) of actual nutrients. The percent of nutrients equals the guaranteed analysis on the bag.

Add the following to Article 253.17 Basis of Payment:

Revised 4/13/06