

20101000	
TEMPORARY FENCE	
LOCATION	FOOT
STA. 146+85, 90' LT. - STA. 150+25, 83.8' LT.	348
STA. 147+25, 87.9' RT. - STA. 150+25, 77.2' RT.	332
TOTAL	680

20200100				
EARTHWORK QUANTITIES				
LOCATION	THEORETICAL		SHORTAGE (-) OR EXCESS (+)	REMARKS
	CUT	FILL		
	CU YD	CU YD	CU YD	
			[(A)0.75]-(B)	
	(A)	(B)	(C)	
IL 72	9	0	7	UNAVAILABLE FOR USE AT IRENE ROAD
IRENE ROAD (ESTIMATE)	14	14	-4	FURNISHED EXCAVATION REQUIRED
				20400800
TOTAL	23	14	3	
	PAY ITEM	FOR INFO ONLY		

28000400	
PERIMETER EROSION BARRIER	
LOCATION	FOOT
AS DIRECTED BY ENGINEER	400
TOTAL	400

28100105	
STONE RIPRAP, CLASS A3	
LOCATION	SQ YD
STA. 140+43, RT.	19
STA. 141+25, RT.	20
STA. 143+24, LT.	4
STA. 145+23, LT.	2
STA. 146+75, LT.	34
STA. 147+00, RT.	33
TOTAL	112

PAVEMENT SCHEDULE											
LOCATION (STA. TO STA.)	35100100 AGGREGATE TYPE A	40200800 AGGREGATE TYPE B *	40500300 BITUMINOUS MIXTURE COMPLETE	40800200 BITUMINOUS MATERIAL (PRIME COAT)	40800300 AGGREGATE (PRIME COAT)	40800400 MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	40800980 BITUMINOUS SURFACE REMOVAL - BUTT JOINT	48101200 AGGREGATE SHOULDER TYPE B	X4066424 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	X4066765 LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	40800040 INCIDENTAL BITUMINOUS SURFACING **
STA 142+00 - STA 142+96.68				0.1			80		24		
STA 142+00 - STA 142+99								7			
STA 142+30 - STA 142+96.68						0.1				12	
STA 145+32.22 - STA. 146+45						0.1				59	
STA 145+32.22 - STA. 146+75				0.1			80		33		
STA 145+49.1 - STA. 146+75								26			
IRENE ROAD	20	6	981	3.6	23		300	146			4
QUARRY ROAD		6	993	3.6	24		133	142			
IRENE ROAD ENTRANCES							45				
TOTAL	20	12	1974	7.4	47	0.2	638	321	57	71	4

BRIDGE APPROACH PAVEMENT SCHEDULE			
LOCATION (STA. TO STA.)	42001165 BRIDGE APPROACH PAVEMENT	42001300 PROTECTIVE COAT	42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)
STA. 142+96.68 - STA. 143+02.68			22
STA. 143+02.68 - STA. 143+32.68	111	111	
STA. 144+96.22 - STA. 145+26.22	111	111	
STA. 145+26.22 - STA. 145+32.22			22
TOTAL	222	222	44

44000100	
PAVEMENT REMOVAL	
LOCATION	SQ YD
STA. 142+96.68 - STA. 143+27.97	48
STA. 145+00.92 - STA. 145+32.22	49
TOTAL	97

4000700	
APPROACH SLAB REMOVAL	
LOCATION	SQ YD
STA. 143+07.97 - STA. 143+27.97	53
STA. 145+00.92 - STA. 145+20.92	53
TOTAL	106

* ESTIMATED QUANTITY FOR AGGREGATE ENTRANCES
 ** ESTIMATED QUANTITY FOR BITUMINOUS ENTRANCES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES FAP 553 (IL 72) SECTION 125VBR-1 DEKALB COUNTY SCALE: VERT. _____ HORIZ. _____ DATE _____	DRAWN BY NJ CHECKED BY JKC
NAME	DATE		
NOE	02/06		

PLOT DATE = 12/06
 FILE NAME = SCHED
 PLOT SCALE = NONE
 USER NAME = CHNS