

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-3)D	JODAVIESS	45	3
STA.	11BR-8	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 100 % STATE	SFTY-3N 100 % STATE	100 STATE SFTY-2A EXIST. SN# 043-0040
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4			
63200310	GUARDRAIL REMOVAL	FOOT	717	717		
63500105	DELINEATORS	EACH	4	4		
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100100	TRAFFIC CONTROL AND PROTECTION STD 701316	EACH	1			1
70100405	TRAFFIC CONTROL AND PROTECTION STD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION STD. 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION STD. 701326	L SUM	1			1
70103815	TRAFFIC CONTROL SURVEILANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1
70300200	TEMPORARY PAVEMENT MARKING	FOOT	3965	2313		1652
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	382	382		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	480	480		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	480	480		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3462	2480		982
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	6	6		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	15	15		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	6	6		
X0323557	BRIDGE JOINT SYSTEM (EXPANSION), 1"	FOOT	74.6			74.6
X0323558	BRIDGE JOINT SYSTEM (EXPANSION) 1-5/8"	FOOT	36	36		
X0712400	TEMPORARY PAVEMENT	SQ YD	24			24
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX "C", N50	TON	118	104		14
X5030305	CONCRETE WEARING SURFACE 5"	SQ YD	977.5	429		548.5
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	72	72		
Z0002600	BAR SPLICERS	EACH	358	197		161
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2	

\* SPECIALTY ITEMS

PLOT DATE = Fri Dec 30 08:22:44 2005  
 PLOT SCALE = 50:0000' / IN.  
 USER NAME = rajnar1

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY