CONTRACT NO. 64B27

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-3)D	JODAVIESS	45	8
STA.	11BR-8	TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200600 EXCAVATING & GRADING EXISTING SHOULDERS

UNIT	LOCATION		
1	18+12	- 23+62	LT & RT
1	TOTAL		

20400800 FURNISHED EXCAVATION

CU YD	LOCATION		
75	18+12	- 23+62	LT & RT
75	TOTAL		

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION		
444	18+04	- 20+21	LT & RT
670	21+28	- 23+86	LT & RT
1114	TOTAL		

28000250 TEMPORARY EROSION CONTROL

POUND	LOCATION		
70	18+04	- 20+21	LT & RT
80	21+28	- 23+86	LT & RT
150	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		
211	18+12	- 20+21	LT
230	18+04	- 20+21	RT
275	21+28	- 23+86	LT
234	21+27	- 23+62	RT
950	TOTAL		

40600530 LEVELING BINDER (MACHINE METHOD) MIX C, TYPE 1, N50

TON	LOCATION	
53	18+42	- 20+21
61	21+28	- 23+40
114	TOTAL	

44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"

SQ YD	LOCATION	
79	18+12	- 18+42
80	23+32	- 23+62
61	317+37	- 317+63
62	319+09	- 319+35
282	TOTAL	

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION		
50	18+04	- 20+21	RT
50	18+51	- 20+21	LT
45	21+28	- 22+90	RT
45	21+28	- 23+86	LT
190	TOTAL		

48200300 BITUMINOUS SHOULDERS 5"

SQ YD	LOCATION		
86	18+12	- 20+06	RT
97	21+44	- 23+62	RT
86	18+12	- 20+06	LT
97	21+44	- 23+62	LT
366	TOTAL		

54200220 PIPE CULVERTS, CLASS D, TYPE 1 15'

FOOT	LOCATION		
50	18+15	- 18+65	RT
50	TOTAL		

54213450 END SECTIONS 15"

EACH	LOCATION	
1	18+65	RT
1	TOTAL	

63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

FOOT	LOCATION		
63	19+25	- 19+88	LT
126	18+62	- 19+88	RT
150	21+62	- 23+12	LT
63	21+62	- 22+25	RT
402	TOTAL		

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION	
1	20+21	LT
1	21+28	LT
1	20+21	RT
1	21+28	RT
4	TOTAL	

63100167 TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION		
1	18+75	- 19+25	LT
1	18+12	- 18+62	RT
1	23+12	- 23+62	LT
1	22+25	- 22+75	RT
4	TOTAL		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Fri Dec 30 09:02:18 2005
FILE NAME = c:\projects\p2019005\d019005cv.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = reynerl