

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
642	(10BR-3D)	JODAVIESS	45	9
STA. 118R-B		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SCHEDULE OF QUANTITIES

63200310	GUARDRAIL REMOVAL				
	<u>FOOT</u>	<u>LOCATION</u>			
	148	18+73 - 20+21	LT		
	211	21+28 - 23+39	LT		
	210	18+11 - 20+21	RT		
	148	21+28 - 22+76	RT		
	717	TOTAL			
63500105	DELINEATORS				
	<u>EACH</u>	<u>LOCATION</u>			
	1	18+75	LT		
	1	18+12	RT		
	1	23+62	LT		
	1	22+75	RT		
	4	TOTAL			
70300200	TEMPORARY PAVEMENT MARKING				
	<u>FOOT</u>	<u>LOCATION</u>			
	638	16+62 - 23+00	YELLOW	STAGE 1	
	511	17+89 - 23+00	WHITE	STAGE 1	
	638	16+62 - 23+00	YELLOW	STAGE 2	
	526	17+74 - 23+00	WHITE	STAGE 2	
	413	315+87 - 320+00	YELLOW	STAGE 1	
	413	315+87 - 320+00	WHITE	STAGE 1	
	413	315+87 - 320+00	YELLOW	STAGE 2	
	413	315+87 - 320+00	WHITE	STAGE 2	
	3965	TOTAL			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL				
	<u>SQ. FT.</u>	<u>LOCATION</u>			
	16	18+14 - 18+88	STAGE 1 CL		
	171	18+14 - 23+34	STAGE 1 WHITE RT		
	24	22+62 - 23+34	STAGE 1 CL		
	171	18+14 - 23+34	STAGE 2 WHITE LT		
	382	TOTAL			
70400100	TEMPORARY CONCRETE BARRIER				
	<u>FOOT</u>	<u>LOCATION</u>			
	480	18+35 - 23+14			
	480	TOTAL			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER				
	<u>FOOT</u>	<u>LOCATION</u>			
	480	18+35 - 23+14			
	480	TOTAL			
78001110	PAINT PAVEMENT MARKING LINE 4"				
	<u>FOOT</u>	<u>LOCATION</u>			
	1100	18+12 - 23+62	WHITE EDGELINES - 2 COATS		
	1100	18+12 - 23+62	WHITE EDGELINES - 2 COATS		
	280	18+12 - 23+62	SKIP DASH YELLOW - 2 COATS		
	436	317+27 - 319+45	WHITE EDGELINES - 2 COATS		
	436	317+27 - 319+45	WHITE EDGELINES - 2 COATS		
	110	317+27 - 319+45	SKIP DASH YELLOW - 2 COATS		
	3462	TOTAL			

78100100	RAISED REFLECTIVE MARKER				
	<u>EACH</u>	<u>LOCATION</u>			
	6	18+12 - 23+62			
	6	TOTAL			
78200410	GUARDRAIL MARKERS, TYPE A				
	<u>EACH</u>	<u>LOCATION</u>			
	2	19+25 - 19+88	LT		
	5	18+62 - 19+88	RT		
	6	21+62 - 23+12	LT		
	2	21+62 - 22+25	RT		
	15	TOTAL			
78201000	TERMINAL MARKER - DIRECT APPLIED				
	<u>EACH</u>	<u>LOCATION</u>			
	1	18+75	LT		
	1	18+12	RT		
	1	23+62	LT		
	1	22+75	RT		
	4	TOTAL			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL				
	<u>EACH</u>	<u>LOCATION</u>			
	6	18+12 - 23+62			
	6	TOTAL			
X0712400	TEMPORARY PAVEMENT				
	<u>SQ. YD.</u>	<u>LOCATION</u>			
	10	317+28 - 317+47	RT		
	14	319+33 - 319+63	RT		
	24	TOTAL			
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE. MIX C. N50				
	<u>TON</u>	<u>LOCATION</u>			
	9	18+12 - 18+42			
	9	23+32 - 23+62			
	40	18+12 - 20+21			
	46	21+28 - 23+32			
	7	317+37 - 317+63			
	7	319+09 - 319+35			
	118	TOTAL			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON -RE-DIRECTIVE), TEST LEVEL 3				
	<u>EACH</u>	<u>LOCATION</u>			
	1	18+35	LT		
	1	23+14	LT		
	2	TOTAL			
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON -RE-DIRECTIVE), TEST LEVEL 3				
	<u>EACH</u>	<u>LOCATION</u>			
	1	18+35	RT		
	1	23+14	RT		
	2	TOTAL			

PLOT DATE = Fri Dec 30 09:45:13 2005
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = reguard

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY