F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(32, 47-4)K	KENDALL/GRUNDY	243	24
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 66294

CULVERT AND STORM SEWER SCHEDULE

STATION	TYPE	TRENCH BACKFILL	PIPE CULVERTS, CLASS A, TYPE 1 (TEMPORARY)			STORM SEWERS, CLASS A										P.R.C. FLARED END SECTIONS				MANHOLE TYPE A, TYPE 1 FRAME							CATCH BASINS			CONCRETE HEADWALL FOR PIPE DRAINS
						TYPE 1	TYPE 2								TYPE 3					CLOSED LID		OPEN LID			CLOSED LID, RESTRICTOR PLATE		TYPE A, 4' DIA.		TYPE C	
			12"	24"	36"	12"	12"	15'	18"	24"	30"	36"	42"	60"	60"	12"	18"	24"	36"	4' DIA.	6' DIA.	5' DIA.	6' DIA.	7' DIA.	6' DIA.	7' DIA.	TYPE 8 GRATE	TYPE 23 FRAME & GRATE	TYPE 8 GRATE	
		CU. YD.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.	EA.
RIDGE ROAD																														
RT 1002+12	CATCH BASIN																											1		
RT 1002+13 TO 1002+13	STORM SEWER	1.1					7																							
LT 1002+91 TO 1002+91	PIPE CULVERT (TEMPORARY)				24																									
RT 1003+18 TO 1003+18	PIPE CULVERT (TEMPORARY)				14																									
LT 1004+23	CATCH BASIN																											1		
LT 1004+23 TO 1004+23	STORM SEWER	0.3					2																							
RT 1004+30	CATCH BASIN																											1		
RT 1004+30 TO 1002+94	STORM SEWER	34.9					133																							
RT 1004+49	CATCH BASIN																										1			
RT 1004+49 TO 1004+30	STORM SEWER	4.1					18																							
LT 1005+95	CATCH BASIN																											1		
LT 1005+95 TO 1005+94	STORM SEWER	0.3					2																							
RT 1006+20	CATCH BASIN																											1		
RT 1006+20 TO 1004+30	STORM SEWER	40.2					186																							
LT 1007+35	MANHOLE																								1					
LT 1007+35 TO 1007+16	STORM SEWER	10.4									17																			
LT 1007+93	MANHOLE																				1									
LT 1007+93 TO 1007+35	STORM SEWER	26.7											53																	
LT 1007+95	CATCH BASIN																											1		
LT 1007+95 TO 1007+93	STORM SEWER	1.3					4																							
RT 1008+00	CATCH BASIN																											1		
RT 1008+00 TO 1007+93	STORM SEWER	16.9					58																							
LT 1008+98	MANHOLE																				1									
LT 1008+98 TO 1007+93	STORM SEWER	53.6											101																	
LT 1009+00	CATCH BASIN																											1		
RT 1009+00	CATCH BASIN																											1		
RT 1009+00 TO 1008+98	STORM SEWER	11.8					58																							
LT 1009+00 TO 1008+98	STORM SEWER	0.6					4																							
LT 1010+33	MANHOLE																				1									
LT 1010+33 TO 1008+98	STORM SEWER	92.8											131																	
LT 1010+35	CATCH BASIN																											1		
LT 1010+35 TO 1010+33	STORM SEWER	0.6					4																							
RT 1010+75	CATCH BASIN																											1		
RT 1010+75 TO 1010+33	STORM SEWER	13.0					71																							
LT 1012+05	MANHOLE																				1									
RT 1012+05	CATCH BASIN																											1		
RT 1012+05	CATCH BASIN																										1			
RT 1012+05 TO 1012+05	STORM SEWER	0.4					5																							
RT 1012+05 TO 1012+05	STORM SEWER	9.1					57																							
LT 1012+05 TO 1010+33	STORM SEWER	188.1											172																	
LT 1012+06	CATCH BASIN																											1		
LT 1012+06 TO 1012+05	STORM SEWER	0.4					4																							

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 80 (I-80 AT MINOOKA INTERCHANGE)

SCHEDULE OF QUANTITIES

SCALE: NONE — DRAWN BY: NJS

DATE: 2/10/06 — CHECKED BY: JJC

PATRICK ENGINEERING INC.
LISLE, ILLINOIS

nschilling(Lisle_Rdwy)
02/10/2006 01:56:07 PM q:\lcct\9391_a0(minooka)\drawings\rdwy\shts\rd\s_sched.dgn