

SUMMARY OF QUANTITIES

← U R B A N →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC	LIGHTING	SIDEWALK	EMERGENCY
				FED 80%	SIGNALS FED 80%		STATE 50%	PREEMPTION
				STATE 20%	STATE 15% CITY 5%		CITY 100%	CITY 100%
				J000-2A	Y031-1F	Y030-1E	SFTY-1B	Y031-3D
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	61	61				
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	228	228				
55034800	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 60, RISE 38	FOOT	433	433				
55100500	STORM SEWER REMOVAL 12"	FOOT	43	43				
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6	6				
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60224445	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1				
60224446	MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4				
60236400	INLETS, TYPE A, TYPE 8 GRATE (24" DEPTH)	EACH	1	1				
60236600	INLETS, TYPE A, TYPE 9 FRAME AND GRATE	EACH	1	1				
60240303	INLETS, TYPE B, TYPE 9 FRAME AND GRATE	EACH	1	1				
60255500	MANHOLES TO BE ADJUSTED	EACH	20	20				
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1				
60260100	INLETS TO BE ADJUSTED	EACH	2	2				
60263105	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3V FRAME AND GRATE	EACH	4	4				
60500060	REMOVING INLETS	EACH	7	7				
60500305	FILLING INLETS	EACH	1	1				
60605000	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24	FOOT	4,448	4,448				
60608600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.06	FOOT	96	96				
60609800	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.18	FOOT	17	17				
60610400	COMBINATION CONCRETE CURB & GUTTER, TYPE M-6.24	FOOT	243	243				
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	S. F.	2,530	2,530				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL. MO.	12	12				
66900200	NON-SPECIAL WASTE DISPOSAL	C. Y.	668	668				
66900450	SPECIAL WASTE PLANS AND REPORTS	L. SUM	1	1				
66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2				
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L. SUM	1	1				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4,356	4,356				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	192	192				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	57	57				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	S. F.	747	747				
*72000100	SIGN PANEL, TYPE 1	S. F.	6.25		6.25			
*72000200	SIGN PANEL, TYPE 2	S. F.	43		43			
72900100	METAL POST - TYPE A	FT.	13		13			
*78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	S. F.	140	140				
*78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	1,630	1,630				
*78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1,194	1,194				
*78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	546	546				
*78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	536	536				
*78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	198	198				
78200300	PRISMATIC CURB REFLECTOR	EACH	24	24				

△ * SPECIALTY ITEMS

REVISED
△ 4-17-06

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
+	+	LASALLE	95	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
+ FAP ROUTE 653 (ROUTE 18 COUPLE)				
+ SECTION (7)R, RS-2; (8)R, RS-1				