

# SUMMARY OF QUANTITIES

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC	LIGHTING	SIDEWALK	EMERGENCY
				FED	SIGNALS		STATE	PREEMPTION
				80%	FED 80%		50%	
				STATE	STATE 15%		CITY	CITY
				20%	CITY 5%	100%	50%	100%
				J000-2A	Y031-1F	Y030-1E	SFTY-1B	Y031-3D
X6020074	INLETS, TYPE A, TYPE 3V FRAME AND GRATE	EACH	19	19				
X6020075	INLETS, TYPE B, TYPE 3V FRAME AND GRATE	EACH	19	19				
*X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1/C	FT.	350	350				
*X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4	4				
*X8801350	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2	2				
*X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2	2				
*X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	8	8				
Z0001050	AGGREGATE SUBGRADE 12"	S. Y.	9,855	9,855				
Z0007601	BUILDING REMOVAL NO. 1	L. SUM	1	1				
Z0007602	BUILDING REMOVAL NO. 2	L. SUM	1	1				
Z0007603	BUILDING REMOVAL NO. 3	L. SUM	1	1				
Z0007604	BUILDING REMOVAL NO. 4	L. SUM	1	1				
Z0007605	BUILDING REMOVAL NO. 5	L. SUM	1	1				
Z0007606	BUILDING REMOVAL NO. 6	L. SUM	1	1				
*Z0049801	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 1	L. SUM	1	1				
*Z0049802	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 2	L. SUM	1	1				
*Z0049803	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 3	L. SUM	1	1				
*Z0049804	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 4	L. SUM	1	1				
*Z0049805	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 5	L. SUM	1	1				
*Z0049806	REMOVAL AND DISPOSAL OF FRIABLE ASBESTOS, BUILDING NO. 6	L. SUM	1	1				
*Z0049901	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 1	L. SUM	1	1				
*Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L. SUM	1	1				
*Z0049903	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 3	L. SUM	1	1				
*Z0049904	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 4	L. SUM	1	1				
*Z0049905	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 5	L. SUM	1	1				
*Z0049906	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 6	L. SUM	1	1				
XX002154	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	4	4				
X0325319	MANHOLES, TYPE A, 8'-DIAMETER, 2 TYPE 1 FRAMES, CLOSED LIDS (SPECIAL)	EACH	1	1				
X0325323	MANHOLES, TYPE A, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3				
X0325320	SANITARY SEWER, PVC SDR 35, 8"	FOOT	464	464				
X0323382	STORM SEWER, WATER MAIN <sup>REQUIREMENTS</sup> TYPE 1 15 INCH	FOOT	44	44				
X0325321	STORM SEWER, WATER MAIN <sup>REQUIREMENTS</sup> TYPE 2 24 INCH	FOOT	131	131				
X0325322	STORM SEWER, WATER MAIN <sup>REQUIREMENTS</sup> TYPE 3 24 INCH	FOOT	73	73				
X0325324	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 7.5"	SQYD	298	298				
② 67100100	MOBILIZATION	L. SUM	1	1				

② \*SPECIALTY ITEMS

② Revised 4-18-06

② REVISED 4-17-06

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
+	+	LASALLE	95	7
STA. TO STA.		FED. ROAD DIST. NO. 3 ILLINOIS FED. AID PROJECT		
+		FAP ROUTE 653 (ROUTE 18 COUPLE)		
+		SECTION (7)R, RS-2; (8)R, RS-1		