CONTRACT NO. 66635 COUNTY TOTAL SHEET NO. SECTION D-3 BRIDGE PAINTING 2006-1 LIVINGSTON & GRUNDY 12 5 **LENGEND** ♠ Roadway ILLINOIS STATE AID PROJECT 6' - 0" 10' - 0" VARIES 12' - 0" 12' - 0" VARIES Work Zone LEFT LANE OPEN ▼ Type II barricade, drum or vertical barricade with stead burn monodirectional light -See Detail A Temporary Pavement Marking Tape Temporary concrete barrier Type C Monodirectional reflector Vertical panel with steady burn monodirectional light Impact attenuator Type C Monodirectional SECTION A-A Reflectors on tangent portion of barrier @ 50' cts. Temporary Concrete Barrier TRAFFIC SIDE DETAIL A 150' 110' LOCATION #1 & #2 10' -STRUCTURE $\rightarrow A$ @--TEMPORARY CONCRETE BARRIER **↓**A (a) Reflectorized temporary pavement marking tape shall be placed throughout the taper and along side the work area. The edge line shall be white for right lane closure. (b) Vertical panels at 25' centers with steady burning monodirectional lights. PLAN ILLINOIS DEPARTMENT OF TRANSPORTATION TRAFFIC CONTROL DETAILS RIGHT LANE CLOSURE Work this sheet with Traffic Control Standards 701400 & 701402 DRAWN BY RW CHECKED BY

LIVINGSTON & GRUNDY COUNTIES

SECTION: D-3 BRIDGE PAINTING 2006-1

FAI 55