

68379

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
380		KNOX	35	7
• D4 CULVERT EXT/REPAIR 2006				

SCHEDULE OF QUANTITIES

STRUCTURES	20800150	50102400	50800105	54002020	54003000	54201273	54201285	54213663	54213675	54248500	54248510	60221100
	TRENCH BACKFILL	CONCRETE REMOVAL	REINFORCEMENT BARS	EXPANSION BOLTS 3/4"	CONCRETE BOX CULVERTS	PIPE CULVERTS, TYPE 2, RCCP 18"	PIPE CULVERTS, TYPE 2, RCCP 30"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	CONCRETE HEADWALLS	CONCRETE COLLAR	MANHOLES, TYPE A, 5'-DIAMETER, TYPE I FRAME, CLOSED LID
LOCATION	CU YD	CU YD	POUND	EACH	CU YD	FOOT	FOOT	EACH	EACH	CU YD	CU YD	EACH
LOCATION 1									1			
Lt 35.43' Sta. 1935+44.75												
From Lt 35.43' Sta. 1935+44.75 To Lt 23.27' Sta. 1935+44.91							12					
Lt 23.27' Sta. 1935+44.91			20	4							0.4	
Rt 24.78' Sta. 1935+45.52		2.5	41								0.7	
From Rt 24.78' Sta. 1935+45.52 To Rt 43.48' Sta. 1935+45.75							19					
Rt 45.82' Sta. 1935.45.78												1
From Rt 47.59' Sta. 1935+47.30 To Rt 63.60' Sta. 1935+60.90							21					
Rt 63.60' Sta. 1935+60.90									1			
LOCATION 2									1			
Lt 17.70' Sta. 1922+04.77												
From Lt 17.70' Sta. 1922+04.77 To Lt 13.89' Sta. 1922+04.75							4					
Lt 13.89' Sta. 1922+04.75		2.2	42								0.8	
Rt 23.37' Sta. 1922+04.64			20	4							0.4	
From Rt 23.37' Sta. 1922+04.64 To Rt 32.92' Sta. 1922+04.61							10					
Rt 32.92' Sta. 1922+04.61									1			
LOCATION 3		1.3						1				
Lt 29.83' Sta. 1867+47.87												
From Lt 29.83' Sta. 1867+47.87 To Lt 16.92' Sta. 1867+47.95							48					
Sta. 1867+47.76	13											
From Rt 15.70' Sta. 1867+47.67 To Rt 18.04' Sta. 1867+47.65								1				
Rt 18.04' Sta. 1867+47.65		2.7										
LOCATION 4										2.95		
Lt 31.04' Sta. 1850+21.95												
From Lt 31.04' Sta. 1850+21.95 To Lt 18.54' Sta. 1850+14.60					5							
Lt 18.54' Sta. 1850+14.60		4.4	1586	14							0.9	
Rt 14.32' Sta. 1849+95.29		2.9	1932	14							0.9	
From Rt 14.32' Sta. 1849+95.29 To Rt 31.03' Sta. 1849+85.47					7							
Rt 31.03' Sta. 1849+85.47										2.95		
TOTAL	13	16	3,641	36	12	48	66	2	4	5.9	4.1	1

28200200	
FILTER FABRIC	
LOCATION	SQ YD
LOCATION 1	
LT STA. 1935+45.20	13
RT STA. 1934+65.26	19
LOCATION 2	
LT STA. 1922+04.71	10
RT STA. 1922+04.71	10
LOCATION 4	
LT STA. 1850+27	48
RT STA. 1850+27	40
TOTAL	140

44200144	
CLASS D PATCHES, TYPE II, 12"	
LOCATION	SQ YD
LOCATION 3	
LT. STA. 1867+47.87	7
RT. STA. 1867+47.87	7
TOTAL	14

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES