

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
380	.	KNOX	35	8
• D4 CULVERT EXT/REPAIR 2006				

## SCHEDULE OF QUANTITIES

28100125	
STONE RIPRAP, CLASS B3	
LOCATION	SQ YD
LOCATION 1	
LT STA. 1935+00 TO STA. 1935+33.68	48
LT STA. 1935+46.55 TO STA. 1936+00	29
RT STA. 1934+50 TO STA. 1935+60.18	100
LOCATION 2	
LT STA. 1921+92.66 TO STA. 1922+02.64	14
LT STA. 1920+10.64 TO STA. 1922+25.64	9
RT STA. 1921+91.64 TO STA. 1922+01.98	10
RT STA. 1922+07.96 TO STA. 1922+17.80	10
LOCATION 3	
LT STA. 1867+47.76	4
RT STA. 1867+47.76	5
TOTAL	229

48101200	
AGGREGATE SHOULDERS, TYPE B	
LOCATION	TON
LOCATION 1	
LT STA. 1934+40 TO STA. 1936+60	9
RT STA. 1933+90 TO STA. 1936+60	13
LOCATION 2	
LT STA. 1921+40 TO STA. 1922+60	6
RT STA. 1921+40 TO STA. 1923+10	8
LOCATION 3	
LT STA. 1867+00 TO STA. 1868+60	8
RT STA. 1866+90 TO STA. 1868+10	6
LOCATION 4	
LT STA. 1849+25 TO STA. 1853+45	20
RT STA. 1848+70 TO STA. 1851+10	11
TOTAL	81

63200310	
GUARDRAIL REMOVAL	
LOCATION	FOOT
LOCATION 1	
STA. 1934+50 TO STA. 1936+20	325
LOCATION 2	
STA. 1921+50 TO STA. 1922+50	75
LOCATION 3	
STA. 1867+00 TO STA. 1868+30	150
LOCATION 4	
STA. 1849+50 TO STA. 1853+00	400
TOTAL	950

67000200	
ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	2
TOTAL	2

67100100	
MOBILIZATION	
LOCATION	EACH
JOBSITE	1
TOTAL	1

50105200	
REMOVE EXISTING CULVERTS	
LOCATION	EACH
STA. 1867+47.76	1
TOTAL	1

66600105	
FURNISH AND ERECT RIGHT OF WAY MARKERS	
LOCATION	EACH
LOCATION 1	
RT 30' STA. 1934+25	1
LT 30' STA. 1934+50	1
LT 60' STA. 1935+25	1
RT 90' STA. 1935+50	1
RT 90' STA. 1935+90	1
LT 60' STA. 1936+00	1
RT 30' STA. 1936+60	1
LT 30' STA. 1936+75	1
LOCATION 2	
RT 35' STA. 1921+50	1
RT 60' STA. 1921+96	1
RT 60' STA. 1922+16	1
RT 35' STA. 1922+60	1
LOCATION 3	
RT 30' STA. 1866+85	1
LT 50' STA. 1867+01.24	1
RT 50' STA. 1867+25	1
RT 50' STA. 1867+60	1
LT 50' STA. 1868+00	1
RT 30' STA. 1867+00	1
LT 30' STA. 1868+50	1
LOCATION 4	
RT 30' STA. 1848+85	1
LT 30' STA. 1849+40	1
RT 50' STA. 1849+40	1
LT 60' STA. 1850+15	1
RT 45' STA. 1850+45	1
RT 30' STA. 1850+90	1
LT 50' STA. 1853+00	1
LT 30' STA. 1853+45	1
TOTAL	27

70100450	
TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

Z0022800	
FENCE REMOVAL	
LOCATION	FOOT
LOCATION 1	
RT. STA. 1934+00 TO STA. 1936+58	258
LOCATION 2	
LT. STA. 1921+50 TO STA. 1923+00	150
RT. STA. 1921+50 TO STA. 1922+60	110
LOCATION 3	
RT. STA. 1867+07.13 , 30.42'-60.00'	30
RT. STA. 1867+0713 TO STA. 1868+78.30	171
LT. STA. 1867+31.40 TO STA. 1868+78.30	73
LOCATION 4	
RT. STA. 1848+70 TO STA. 1850+90	220
LT. STA. 1850+65, 33' TO STA. 1850+65, 75'	42
LT. STA. 1850+65 TO STA. 1853+45	280
TOTAL	1,334

Z0013798	
CONSTRUCTION LAYOUT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

Z0073100	
TEMPORARY SHORING	
LOCATION	EACH
LOCATION 1	
RT. STA. 1935+45.20	1
LOCATION 4	
LT. STA. 1850+03.98	1
TOTAL	2

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULE OF QUANTITIES