

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	D4 BRIDGE REP.	TAZENWELL	24	4
STA. 250+19.48		TO STA. 250+19.48		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SCHEDULE OF QUANTITIES

MOBILIZATION

JOBSITE = 1.0 LSUM

T. C. & P, STANDARD 701 400

JOBSITES = 2.0 EACH

T. C. & P, STANDARD 701 401

JOBSITES = 2.0 EACH

T. C. & P, STANDARD 701 501

JOBSITES = 2.0 EACH

T. C. & P, STANDARD 701 601

JOBSITE = 1.0 EACH

EPOXY PAVEMENT MARKING LINE - 4''

VARIOUS JOBSITES = 3690 FOOT

EPOXY PAVEMENT MARKING LINE - 12''

LICK CREEK JOBSITE = 131 FOOT

CONCRETE SEALER

S. N. 090-0134 AND
S. N. 090-0135 DECK = 1387 SQ. YD.

CONCRETE HEALER SEALER

S. N. 090-0089 & 090-0131 DECK = 3154 SQ. YD.

CONCRETE METHACRYLATE SEALER

S. N. 090-0146 DECK = 779 SQ. YD.

090-0089	FONDULAC DR.	MARK 135	HEALER SEALER
090-0131	S. MAIN ST.(MORTON)	DURAL 335	HEALER SEALER
090-0134	S.B. I-155 over IL. 9	WATER REPELLENT #2	SEALER
090-0135	N.B. I-155 over IL. 9	CLEAR MASONRY SEALER	SEALER
090-0146	IL. 98 over Lick Crk.	DURAGUARD 401	METHACRYLATE SEALER

DATE: * DATE *
FILE NAME: * FILE *
PLOT SCALE: * SCALE *
REFERENCE: * REF *

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE 12-03-2003

DRAWN BY CEJ
CHECKED BY