

SUMMARY OF QUANTITIES

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
685	(39BR)I	FULTON	22	3
STA.		TO STA.		
EXISTING CONDITIONS:				
CONTRACT NO. 68497				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X080-2A 80% FED 20% STATE						
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	148	148						
40600300	AGGREGATE (PRIME COAT)	TON	1	1						
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	160	160						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2	2						
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1		1					
50102400	CONCRETE REMOVAL	CU YD	4.8		4.8					
50300225	CONCRETE STRUCTURES	CU YD	6.1		6.1					
50300260	BRIDGE DECK GROOVING	SQ YD	506		506					
50300300	PROTECTIVE COAT	SQ YD	537		537					
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	4,824		4,824					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8,290		8,290					
*50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	269			269				
51500100	NAME PLATES	EACH	1		1					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4						
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	100			100				
*63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4			4				
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3			3				
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	160			160				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4						
67100100	MOBILIZATION	L SUM	1	1						
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	120	120						
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1			1				
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12						
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	176							
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7,040							
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,405	2,405			176			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500	500			7,040			
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500	500						
*78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	3,520							
78200410	GUARDRAIL MARKERS, TYPE A	EACH	4			4				
78200510	BARRIER WALL MARKERS, TYPE A	EACH	4	4			3,520			
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3			3				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,173	1,173						

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	X080-2A 80% FED 20% STATE						
Z0002600	BAR SPLICERS	EACH	151			151				
○ Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	2							2
○ Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	2							2
X0325294	PREFORMED JOINT STRIP SEAL	FOOT	41.5			41.5				
X4066614	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N50	TON	8		8					
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	37		37					
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	537		537					
* X7200200	WIDE LOAD SIGNING	L SUM	1		1					

* SPECIALTY ITEMS
○ SFTY-3N

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAP ROUTE 685
SECTION (39BR)I
FULTON COUNTY

SCALE: NONE DRAWN BY: KBF
DATE: 2/10/2006 CHECKED BY: BWP