

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
323	045,146IL	EDGAR	9	3

SUMMARY OF QUANTITIES

LOCATION OF WORK: U. S. RTE 36
&
IL. RTE 49
INTERSECTION
EDGAR COUNTY
HIGHWAY LIGHTING
MAINTENANCE FUND
100% STATE

CONSTRUCTION TYPE CODE: Y030-1E

CODE NO	ITEM	UNIT	TOTAL QUANTITY
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
80500100	SERVICE INSTALLATION TYPE A	EACH	1.0
80802300	WOOD POLE, 40 FT., CLASS 3	EACH	2.0
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	265.0
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	191.0
81600215	UNIT DUCT, 2*8XLP, 1*8 XLP GROUND 3/4" POLYETHYLENE	FOOT	468.0
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4.0
83002500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. DAVIT ARM	EACH	4.0
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	24.0
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	16.0
84200600	REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE	EACH	8.0
84200800	POLE FOUNDATION, REMOVED	EACH	7.0
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	1.0
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	1.0
87200400	SPAN WIRE	FOOT	199.0
87200500	TETHER WIRE	FOOT	199.0
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	24.0
87302225	ELECTRIC CABLE AERIAL SUSPENDED, SIGNAL, NO. 14 3C	FOOT	258.0
89502400	REMOVE EXISTING FLASHING BEACON INSTALLATION COMPLETE	EACH	1.0
X0323134	REMOVE EXISTING HELIX FOUNDATION	EACH	1.0
X8250207	LIGHTING CONTROLLER PHOTOCELL RELAY, SPECIAL	EACH	1.0
X8801505	SIGNAL HEAD, POLYCARBONATE, LED, 4-FACE, 1-SECTION, SPAN WIRE MOUNTED	EACH	2.0