

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	RS, R	••	302	TA
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

• FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)
 ** MONTGOMERY & MACOUPIN COUNTIES
CONTRACT NO. 72526

CODED NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY 80% FEDERAL 20% STATE	MONTGOMERY COUNTY				MACOUPIN COUNTY					
				TRAFFIC SIGNALS FAU 8239 - URBAN OLD US 66 & IL ROUTE 16 Y031-1F	ROADWAY FAU 8239 - URBAN BITUMINOUS RESURFACING NORTH PROJECT LIMITS TO STA 688+28.13 BK NB & SB STA 688+48.07 AH TO STA 690+15.7 NB & SB STA 690+15.7 TO STA 780+75.59 SB STA 750+19.70 TO STA 780+75.59 NB IL RTE 16 STA 922+02.0 TO STA 924+67.0 1000-2A	ROADWAY FAU 8239 - URBAN PORTLAND CEMENT CONCRETE RECONSTRUCTION TO STA 750+20.0 NB J000-2A	ROADWAY FAS 1767 - RURAL BITUMINOUS RESURFACING STA 780+75.59 TO STA 842+76.49 BK STA 843+89.12 AH TO STA 981+68.70 1000-2A	ROADWAY FAS 1766 - RURAL BITUMINOUS RESURFACING STA 981+68.70 TO STA 1010+89.70 BK STA 1025+03.03 AH TO STA 1297+00.00 BK STA 50+00.00 AH TO STA 76+72.05 BK STA 109+00.00 AH TO STA 120+90.00 IL RTE 138 - STA 112+63.04 TO STA 124+47.17 1000-2A	ROADWAY SBI 16 - RURAL BITUMINOUS RESURFACING STA 60+90.71 TO STA 40+00 BK STA 1136+96.28 AH TO STA 1176+35.97 BK STA 70+00.00 AH TO STA 64+53.12 1000-2A	TRAFFIC SIGNALS FAS 1766 - RURAL OLD US 66 & IL ROUTE 138 Y031-1F			
X4409410	BITUMINOUS SURFACE REMOVAL, 2 1/4"	SO YD	1,405										
X6063600	COMBINATION CONCRETE CURB AND GUTTER, M-4.24	FOOT	85.5										
X6064201	COMBINATION CONCRETE CURB AND GUTTER, M-4.06	FOOT	44.0										
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1										
* X8801100	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 1-SECTION, POST MOUNTED	EACH	2										2
* X8801300	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4		4								
* X8950910	REBUILD EXISTING SIGNAL HEAD FACE, 3-SECTION, LED	EACH	10		10								
* X8950920	REBUILD EXISTING SIGNAL HEAD FACE, 5-SECTION, LED	EACH	4		4								
Z0013825	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	250									250	
⊙ Z0014800	CULVERTS TO BE CLEANED	FOOT	919			310		78				300	231
Z0064225	SEALING ABANDONED WATER WELLS	EACH	1			1							
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1			0.5		0.5					
XO 325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	2.1			0.4		1.0				0.7	
XO 325284	REBUILD EXISTING SIGNAL HEAD FACE, 1-SECTION, LED	EACH	2										2
XO 325280	MEDIAN INLET LID REMOVAL	EACH	6			1		3				2	
XO 325281	CULVERT REPAIR	EACH	6					1				5	
XO 325285	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 1 1/2"	SO YD	930			930							
XO 325282	PORTLAND CEMENT CONCRETE SURFACE REMOVAL, 1/4"	SO YD	4,140									4,140	
XO 325283	BITUMINOUS SHOULDER REMOVAL AND REPLACEMENT 8"	SO YD	4,800			810		2,010				1,980	

⊙ 100% STATE
 * SPECIALTY ITEMS

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<p style="text-align: center;">SUMMARY OF QUANTITIES</p> <p>SCALE: VERT. HORIZ. DATE 2/8/2006</p> <p style="text-align: right;">DRAWN BY TJD CHECKED BY AWB</p>	