

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	RS, R	••	302	7
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

\* FAU 8239, FAS 1767, FAS 1766 & SBI 16 (OLD US 66)  
 \*\* MONTGOMERY & MACOUPIN COUNTIES

**CONTRACT NO. 72526**

CODED NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY 80% FEDERAL 20% STATE	CONSTRUCTION CODE						
				MONTGOMERY COUNTY			MACOUPIN COUNTY			
				TRAFFIC SIGNALS FAU 8239 - URBAN OLD US 66 & IL ROUTE 16  Y031-1F	ROADWAY FAU 8239 - URBAN BITUMINOUS RESURFACING NORTH PROJECT LIMITS TO STA 688+28.13 BK NB & SB STA 688+48.07 AH TO STA 690+15.7 NB & SB STA 690+15.7 TO STA 780+75.59 SB STA 750+19.70 TO STA 780+75.59 NB IL RTE 16 STA 922+02.0 TO STA 924+67.0  1000-2A	ROADWAY FAU 8239 - URBAN PORTLAND CEMENT CONCRETE RECONSTRUCTION STA 690+15.7 TO STA 750+20.0 NB  J000-2A	ROADWAY FAS 1767 - RURAL BITUMINOUS RESURFACING STA 780+75.59 TO STA 842+76.49 BK STA 843+89.12 AH TO STA 981+68.70  1000-2A	ROADWAY FAS 1766 - RURAL BITUMINOUS RESURFACING STA 981+68.70 TO STA 1010+89.70 BK STA 1025+03.03 AH TO STA 1297+00.00 BK STA 50+00.00 AH TO STA 76+72.05 BK STA 109+00.00 AH TO STA 120+90.00 IL RTE 138 - STA 112+63.04 TO STA 124+47.17  1000-2A	ROADWAY SBI 16 - RURAL BITUMINOUS RESURFACING STA 60+90.71 TO STA 40+00 BK STA 1136+96.28 AH TO STA 1176+35.97 BK STA 70+00.00 AH TO STA 64+53.12  1000-2A	TRAFFIC SIGNALS FAS 1766 - RURAL OLD US 66 & IL ROUTE 138  Y031-1F
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	358					274	84	
78200300	PRISMATIC CURB REFLECTOR	EACH	81					81		
78200405	GUARDRAIL MARKERS	EACH	14					14		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6					6		
78300100	PAVEMENT MARKING REMOVAL	SO FT	1,612		47		30	1,535		
81012500	CONDUIT IN TRENCH, 1 1/2" DIA. PVC	FOOT	373							373
81012600	CONDUIT IN TRENCH, 2" DIA. PVC	FOOT	33							33
81021540	CONDUIT, AUGERED, 1 1/2" DIA. PVC	FOOT	232							232
81021550	CONDUIT, AUGERED, 2" DIA. PVC	FOOT	80							80
81100500	CONDUIT ATTACHED TO STRUCTURE, 1 1/2" DIA. GALVANIZED STEEL	FOOT	28							28
81306100	JUNCTION BOX (SPECIAL)	EACH	1							1
81400100	HANDHOLE	EACH	2							2
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	406							406
83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8"	EACH	1						1	
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	4						4	
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1						1	
85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1	1						
85900100	TRANSCEIVER	EACH	1	1						
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2/C	FOOT	936							936
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 6 PAIR	FOOT	959	959						
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	4	4						
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	1,112	1,015						97
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1						
89502380	REMOVE EXISTING HANDHOLE	EACH	3							3
X0300015	CONCRETE WINGWALL REMOVAL	EACH	3		2			1		
X0301735	CONCRETE HEADWALL REPAIR	EACH	1				1			
X0320872	VIDEO VEHICLE DETECTION SYSTEM	EACH	1	1						
X0322178	REMOVE EXISTING LIGHT POLE FOUNDATION	EACH	1						1	
X0322729	MATERIAL TRANSFER DEVICE	TON	16,951		3318		4496	7655	1482	
X0323153	ELECTRIC CABLE IN CONDUIT GROUND, NO. 6 1/0 GREEN	FOOT	1,175	1,175						
X0549200	CLEANING PAVED DITCH	FOOT	632					632		
X3560130	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE, 9"	SO YD	4,571					1,145	3,426	
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	18,177		3,572	50	4,619	8,424	1,512	
X4066765	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N50	TON	10,219		1,202	25	2,351	5,442	1,199	

△ SFTY-3C  
 \* SPECIALTY ITEMS  
 © 100% STATE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 SCALE: VERT.  
 HORIZ.  
 DATE 2/8/2006  
 DRAWN BY TJD  
 CHECKED BY AWM

Rev.