

CONTRACT NO. 72680

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
			80% FEDERAL 20% STATE	ROADWAY I000-2A	WETLAND MITIGATION Y077	CULVERT STA 960+46.00 X028-2A	BRIDGE SEC 34-4B STA 973+28.00 X081-2A	BRIDGE SEC 34-4B-1 STA 1153+07.72 X071-2A	IMPACT ATTENUATORS SFTY-3N	HIGHWAY LIGHTING YO30-1E	
54248510	CONCRETE COLLAR	CU YD	11	11							
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	80	80							
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	418	418							
58700200	BRIDGE SEAT SEALER	SQ FT	266						266		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	291				235		56		
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	279	279							
60100915	PIPE DRAINS 6"	FOOT	400	400							
60100925	PIPE DRAINS 8"	FOOT	400	400							
60100935	PIPE DRAINS 10"	FOOT	200	200							
60100945	PIPE DRAINS 12"	FOOT	200	200							
60100955	PIPE DRAINS 15"	FOOT	200	200							
60105000	PIPE DRAINS, CORRUGATED STEEL OR ALUMINUM ALLOY 12"	FOOT	20	20							
60107600	PIPE UNDERDRAINS 4"	FOOT	83,308	83,308							
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	4,440	4,440							
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	434				330		104		
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3							
60222805	MANHOLES, TYPE A, 5'-DIAMETER, WITH MEDIAN INLET (604106)	EACH	9	9							
60223100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5							
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1							
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE1 FRAME, CLOSED LID	EACH	1	1							
60246605	MEDIAN INLET (604101)	EACH	9	9							
60246805	MEDIAN INLET (604106)	EACH	1	1							
60500060	REMOVING INLETS	EACH	4	4							

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

FAP ROUTE 315
SUMMARY OF QUANTITIES

DATE 1/31/06

DRAWN BY TJD
CHECKED BY JRB