CONTRACT NO. 72A22

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	*	CHRISTIAN	8	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D6 BUILDING DEMOLITION 2006

GENERAL NOTES

1. SEEDING WILL NOT BE PERMITTED AT ANY TIME WHEN THE GROUND IS FROZEN, WET OR IN AN UNTILLABLE CONDITION. LOCATIONS TO BE SEEDED SHALL BE DETERMINED BY THE ENGINEER.

2. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCE NOTICE IS REQUIRED. ANY DAMAGE TO THE UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR, SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE, INCLUDING TEMPORARY REPAIRS WHICH MAY BE REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIALS IS BEING OBTAINED TO MAKE PERMANENT REPAIRS.

3. ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.

COMMITMENTS

THERE ARE NO COMMITMENTS ON THIS PROJECT.

DISTRICT SIX

EXAMINED January 26 20 06

OPERATIONS ENGINEER

EXAMINED FEB 15 20 06

PROGRAM IMPLEMENTATION ENGINEER

EXAMINED February 15 20 06

PROGRAM DEVELOPMENT ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES

FAP 322 (US 51)
SECTION D6 BUILDING DEMOLITION 2006
CHRISTIAN COUNTY

SCALE: VERT. HORIZ. DRAWN BY

DATE CHECKED BY

PLOT DATE = 2/13/2006
FILE NAME = S:\Bdy Demo\D-96-097-06 (US 51 Bldg Demo)\Powerdraft Files\Vol 2 buildings\sht\generalnotes.dgn
PLOT SCALE = 108.4337 ' / IN.
USER NAME = mgerrip