

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	MARION	13	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• D-7 JOINT REPAIRS 2006-1				

PAVING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS SURFACE REMOVAL 1 1/2"	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105
	LIN FT	FEET	SQ. YD.	GAL	SQ. YD.	TON
PASSING LANE SHOULDER						
1876+55 TO 1885+78	923	6	615	62	615	52
1887+62 TO 1890+12	250	6	167	17	167	14
DRIVING LANE SHOULDER						
1876+55 TO 1885+96	941	5	523	52	523	44
1887+78 TO 1890+12	234	5	130	13	130	11
TOTALS:			1435	143	1435	121

STRIPING SCHEDULE

STATION TO STATION	LENGTH	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	POLYUREA PAVEMENT MARKING - LINE 4"	PAVEMENT MARKING REMOVAL	
	LIN FT	FOOT	SQ. FT.	FOOT	FOOT	
DRIVING LANE						
1870+72 TO 1876+55	583	0	195	0	0	
1876+55 TO 1888+12	1157	1160	773	1160	386	
1888+12 TO 1890+12	200	200	67	200	67	
PASSING LANE						
1870+72 TO 1876+55	583	0	195	0	0	
1876+55 TO 1888+12	1157	1160	773	1160	386	
1888+12 TO 1890+12	200	200	67	200	67	
TOTALS:			2720	2070	2720	905

PLOT DATE = 2/10/2006
 PLOT SCALE = 50.0000 / IN.
 USER NAME = staffennk

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DRAWN BY
 HORIZ. CHECKED BY
 DATE