

SCHEDULE OF QUANTITIES

| SCHEDULE OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE YO-31F | | |
|------------------------|--|-------|------------------|-------------------------------|-------|-------|
| CODE NO | ITEM | UNIT | | ----- | ----- | ----- |
| 72000100 | SIGN PANEL - TYPE 1 | SQ FT | 25 | | | |
| 80500100 | SERVICE INSTALLATION, TYPE A | EACH | 1 | | | |
| 80801500 | WOOD POLE, 25 FT., CLASS 5 | EACH | 1 | | | |
| 81000500 | CONDUIT IN TRENCH, 1 1/2" DIA., GALVANIZED STEEL | FOOT | 4 | | | |
| 81012300 | CONDUIT IN TRENCH, 1" DIA., PVC | FOOT | 86.5 | | | |
| 81012500 | CONDUIT IN TRENCH, 1 1/2" DIA., PVC | FOOT | 529 | | | |
| 81012600 | CONDUIT IN TRENCH, 2" DIA., PVC | FOOT | 28 | | | |
| 81012700 | CONDUIT IN TRENCH, 2 1/2" DIA., PVC | FOOT | 6 | | | |
| 81012800 | CONDUIT IN TRENCH, 3" DIA., PVC | FOOT | 29 | | | |
| 81018500 | CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL | FOOT | 45 | | | |
| 81018600 | CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL | FOOT | 129 | | | |
| 81400400 | CONCRETE HANDHOLE | EACH | 5 | | | |
| 81400600 | CONCRETE DOUBLE HANDHOLE | EACH | 1 | | | |
| 81500200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | FOOT | 658.5 | | | |
| 81702130 | ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6 | FOOT | 858.5 | | | |
| 85700200 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET | EACH | 1 | | | |
| 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 185.5 | | | |
| 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 199.5 | | | |
| 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 1440.5 | | | |
| 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 1521 | | | |
| 87301305 | ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR | FOOT | 2269 | | | |
| 87301815 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C | FOOT | 14 | | | |
| 87700180 | STEEL MAST ARM ASSEMBLY AND POLE, 28 FT. | EACH | 1 | | | |
| 87700220 | STEEL MAST ARM ASSEMBLY AND POLE, 36 FT. | EACH | 2 | | | |
| 87700240 | STEEL MAST ARM ASSEMBLY AND POLE, 40 FT. | EACH | 1 | | | |
| 87800200 | CONCRETE FOUNDATION, TYPE D | FOOT | 3 | | | |
| 87800400 | CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER | FOOT | 10 | | | |
| 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 35 | | | |
| 88200100 | TRAFFIC SIGNAL BACKPLATE | EACH | 10 | | | |

| SCHEDULE OF QUANTITIES | | | TOTAL QUANTITIES | CONSTRUCTION TYPE CODE YO-31F | | |
|------------------------|--|------|------------------|-------------------------------|-------|-------|
| CODE NO | ITEM | UNIT | | ----- | ----- | ----- |
| 88500100 | INDUCTIVE LOOP DETECTOR | EACH | 13 | | | |
| 88600100 | DETECTOR LOOP, TYPE I | FOOT | 1795.5 | | | |
| 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 2 | | | |
| 89502375 | REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT | EACH | 1 | | | |
| 89502385 | REMOVE EXISTING CONCRETE FOUNDATION | EACH | 3 | | | |
| X8801300 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED | EACH | 4 | | | |
| X8801310 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED | EACH | 6 | | | |
| X8801345 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED | EACH | 2 | | | |
| X8801350 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED | EACH | 2 | | | |
| X8801385 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED | EACH | 2 | | | |
| X8801400 | SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED | EACH | 2 | | | |
| X8810395 | PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED | EACH | 2 | | | |