CONTRACT NO. 76952

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	66-31	MONROE	45	4
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A URBAN FEDERAL 90% STATE 10%	Y031-1F URBAN FEDERAL 90% STATE 5% CITY 5%	
X4066538	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90	TON	151	151		
X4066618	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90	TON	344	344		
X4073161	BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 14"	SQ YD	1176	1176		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	1	1		
X7240500	RELOCATE EXISTING SIGNS	EACH	6	6		
* X8801300	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		1	
* X8801310	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	1		1	
* X8801400	SIGNAL HEAD ,POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1		1	
* X8950200	REBUILD EXISTING HANDHOLE	EACH	2		2	
* X8950210	REBUILD EXISTING HANDHOLE TO HEAVY-DUTY HANDHOLE	EACH	1		1	
Z0000990	AGGREGATE FOR TEMPORARY ACCESS	TON	78	78		
Z0036200	PAINT CURB	FOOT	80	80		

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	I000-2A URBAN FEDERAL 90% STATE 10%	Y031-1F URBAN FEDERAL 90% STATE 5% CITY 5%	

Rev.

PLOT DATE = 2/9/2006
FILE NAME = c:\projects\sd09305\plan\pln09305a.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF