CONTRACT NO. 76952

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	66-3I	MONROE	45	11
STA. _____		TO STA._____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

PAVING AND RESURFACING SCHEDULE

LOCATION	BITUMINOUS SURFACE REMOVAL 2 IN (SQ YD)	BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	BIT CONC BINDER CSE SUPER, IL-19.0 N 90 9" (TON)	BIT CONC BINDER CSE SUPER, IL-19.0 N 90 6" (TON)	STRIP REFL CRACK CONT TREATMENT (FT)	INCIDENTAL BITUMINOUS SURFACING (TON)	POLY BIT CONC SURF CSE SUPER MIX E N90 2" (TON)	BIT CONC BINDER CSE SUPER, IL-19.0 N 90 12" (TON)	BIT CONC PAVEMENT (FULL-DEPTH) SUPER, 14" (SQ YD)	BITUMINOUS SHOULDERS SUPERPAVE 8" RIGHT SIDE (SQ YD)	AGGREGATE SHOULDERS TYPE B RIGHT SIDE (TON)
NORTH MAIN STREET												
STA.116+28 TO 114+92				56				12			75	
STA.114+92 TO 113+89	108	0.03	0.2	80		109		17				5
STA.113+89 TO 113+56	56	0.02	0.1					6				6
STA.634+01 N. MAIN ST. TO												
STA.632+92 NB IL 3	163	0.05	0.2					18				7
STA.632+92 TO 632+35	131	0.04	0.2	18		64		18				8
STA.632+35 TO 631+82	228	0.07	0.3	30		53		32			25	
STA.631+82 TO 623+00										1,176	424	
STA.623+00 TO 620+12	256	0.08	0.4			288		47	113		104	
(ON RAMP)												
DALEVIEW DRIVE					47		15					
TOTALS	942	0.3	2	184	47	514	15	151	113	1,176	628	27

NOTES:

1. BITUMINOUS CONCRETE PAVEMENT (FULL-DEPTH), SUPERPAVE, 14" WILL CONSIST OF 2 INCHES OF POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N90 AND 12 INCHES OF BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N90.

2. REFER TO PLAN SHEETS 18 - 21 FOR PAY LIMITS FOR THE VARIOUS BITUMINOUS PAY ITEMS.

PAVEMENT MARKING SCHEDULE

LOCATION	SOLID WHITE 4" (FT)		SKIP-DASH WHITE 4" (FT)	SOLID WHITE 8" (FT)	DIAGONAL WHITE 12" (FT)	PAINT CURB (FT)	SOLID WHITE 24" (FT)	SOLID WHITE LETTERS AND SYMBOLS (SQ FT)		PRISMATIC CURB REFLECTOR (EACH)	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)
	EDGELINES	LANE LINE	ABBREVIATED LANE LINE	LANE LINE	MEDIAN	MEDIAN	STOP BARS	RIGHT TURN ARROW	COMB. LEFT TURN/ THROUGH ARROW	ONE-WAY CRYSTAL	ONE-WAY CRYSTAL
NORTH MAIN STREET											
STA.116+56 TO 116+16	40										
STA.116+16 TO 114+16	116		50								
STA.114+16 TO 113+62	54	54						8.8	14.7		3
INTERSECTION/MEDIAN	163			346	77	80	18	8.8	14.7	13	19
NORTHBOUND IL 3											
STA.631+92 TO 621+00	1092		273								
STA.621+00 TO 620+12	88			88							3
TOTALS	1553	54	323	434	77	80	18	17.6	29.4	13	25

NOTE: ALL PAVEMENT MARKING LINES AND SYMBOLS ARE THERMOPLASTIC EXCEPT "PAINT CURB".

PLOT DATE = 2/8/2006
FILE NAME = c:\pw_pw1\d95305\plan\pln093805c.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = $$REF$

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 312 (IL 3)
SECTION 66-3I
MONROE COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY