

# SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592	1211-1	ST. CLAIR	16	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FED 10% STATE 1000-1A	
20200100	EARTH EXCAVATION	CU YD	232	232	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25100115	MULCH, METHOD 2	ACRE	0.1	0.1	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	10	10	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	71	71	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	466	466	△
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	247	247	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.7	0.7	
40600300	AGGREGATE (PRIME COAT)	TON	3	3	
40600990	TEMPORARY RAMP	SQ YD	71	71	
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1971	1971	
44000100	PAVEMENT REMOVAL	SQ YD	406	406	
44003100	MEDIAN REMOVAL	SQ FT	652	652	△
44004250	PAVED SHOULDER REMOVAL	SQ YD	160	160	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ YD	16	16	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	739	739	
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8"	SQ YD	161	161	△
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	468	468	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	1167	1167	△
<del>60619600</del>	<del>CONCRETE MEDIAN, TYPE SB-6.12</del>	<del>SQ FT</del>	<del>208</del>	<del>208</del>	<del>△</del>
63300900	VERTICAL ADJUSTMENT OF GUARD RAIL	FOOT	24	24	
63300930	VERTICAL ADJUSTMENT OF TRAFFIC BARRIER TERMINAL, TYPE 1A	EACH	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	405	405	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	93	93	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3082	3082	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	224	224	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1324	1324	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 90% FED 10% STATE 1000-1A	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	9	9	
* 73000100	WOOD SIGN SUPPORT	FOOT	29	29	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	93	93	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3082	3082	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	224	224	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	26	26	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	34	34	
* 78200300	PRISMATIC CURB REFLECTOR	EACH	24	24	
X3560140	BITUMINOUS CONCRETE BASE COURSE WIDENING, SUPERPAVE 10 INCH	SQ YD	135	135	△
X4066426	<del>POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N 70</del>	TON	167	167	△
* X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SQ FT	219	219	
* X7800200	PAINT PAVEMENT MARKING CURB	FOOT	124	124	

\*SPECIALTY ITEMS

Rev. 4-11-06