CONTRACT NO. 76956

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
592	121I-1	ST. CLAIR	16	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

RESURFACING SCHEDULE

LOCATION STA	TO	STA	BIT. MAT'L PRIME COAT (TON)	AGGREGATE PRIME COAT (TON)	SURFACE COURSE (TON)	PAVED SHOULDER REMOVAL (SQ YD)	BITUMINOUS SURFACE (VARIABLE DEPTH) (SQ YD)	BITUMINOUS BASE COURSE WIDENING 10" (SQ YD)	AGGREGATE BASE COURSE TYPE B (SQ YD)	BITUMINOUS SHOULDER 8" (SQ YD)	STRIP REFLECTIVE CRACK CONTROL TREATMENT (FOOT)	TEMPORARY RAMPS (SQ YD)
IL 157												
276+15.58	TO	277+50.21	0.07	0.36	20.41	44.88	265.52			45		8.33
277+50.21	TO	277+96.45	0.04	0.17	9.36	15.41	111.44			18		
277+96.45	TO	278+32.40	0.03	0.15	8.61	11.98	62.47	7.98	27.68	12	203.95	
278+32.40	TO	278+58.61	0.02	0.09	5.09	8.74	45.84	5.82	27.11	7	26.21	
278+58.61	TO	279+11.27	0.04	0.2	11.07	17.55	90.98	17.4	55.39	18	52.66	
279+11.27	TO	279+65.11	0.05	0.22	12.3	17.95	87.68	28.23	110	18	53.84	
279+65.11	TO	279+82.74	0.02	0.1	5.37	5.88	53.93	12.01	218.75	6	17.63	
279+82.74	TO	280+94.37	0.10	0.45	25.18	37.21	196.72	63.5	27.03	37	258.89	
280+94.37	TO	281+30.00	0.02	0.12	6.47		54.28					19.78
281+30.00	TO	284+00.00	0.17	0.82	45.79		496.21				92.16	34.66
284+00.00	TO	285+03.88	0.06	0.31	17.48		161.04				32.92	7.55
TOTAL =			0.7	3	167	160	1627 △1	135	466 △1	161	739	71

MEDIAN SCHEDULE

LOCATION			PAVEMENT REMOVAL	SUB-BASE GRANULAR MATERIAL TYPE A 4"	P.C.C. BASE COURSE WIDENING, 10"	COMBINATION CURB & GUTTER	CONCRETE MEDIAN SURFACE 4"	CONCRETE MEDIAN	MEDIAN REMOVAL
			SQ YD	SQ YD	SQ YD	FOOT	SQ FT	SQ FT	SQ FT
277+96.45	TO	279+65.11	188.00		91.73	231.15	473.05	107.00	
279+82.74	TO	281+30.00	217.30 △1		87.36	235.95	693.87	102.00	
281+96.56	TO	282+17.59		11.50	11.50				103.64
282+72.84	TO	282+94.47		12.24	12.24				109.88
283+48.79	TO	283+96.29		25.35	25.33				233.70
284+62.35	TO	285+03.88	△1	17.80	17.80				204.33
								43.00	
TOTALS			406 △1	67	247 △1	468	1167 △1	252 △1	652 △1

PAVEMENT MARKING

LOCATION STATION	TO	STATION	THERMOPLASTIC PAVEMENT MARKING 4" SOLID YELLOW EDGE LINE	4" SOLID WHITE LANE LINE	4" SOLID WHITE EDGE LINE	4" SOLID WHITE DASHED	4" SOLID DOUBLE YELLOW LINE - MEDIAN	12" SOLID YELLOW DIAGONAL	24" RAILROAD GRADE-CROSSING	LETTERS & SYMBOLS RIGHT TURN ARROW	RAISED REFLECTIVE PAVEMENT MARKERS ONE WAY CRYSTAL	RAISED REFLECTIVE PAVEMENT MARKERS ONEWAY AMBER	PRISMATIC CURB REFLECTORS	PAINT PAVEMENT MARKING-RAISED MEDIAN	PAINT PAVEMENT MARKING CURB
			FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ YD	EACH △1	EACH	EACH	SQ FT	FOOT
IL 157															
276+16	TO	276+50			34	22									
276+50	TO	277+00			50	26									
277+00	TO	277+50			50	26	77	1				2			
277+50	TO	278+00			50		200	7				4			
278+00	TO	278+50			50		136	6				2	3	30.5	8.5
278+50	TO	279+00	100		50								2		44
279+00	TO	279+50	100	39	50					15.6	2		2		43.5
279+50	TO	280+00	76	50	50						3		8	66	25
280+00	TO	280+50	100	50	50						2		2		44
280+50	TO	281+00	100	50	50					15.6	3		4		42
281+00	TO	281+50	37	5	3								3	27.5	12
281+50	TO	282+00			13		4								
282+00	TO	282+50			50		100	41				2			
282+50	TO	283+00			50		200	38				4			
283+00	TO	283+50			50		200	25	13	61.2		2			
283+50	TO	284+00			50		200	31	13			2			
284+00	TO	284+50			50		200	38				2			
284+50	TO	285+00			50		180	37				4			
285+00	TO	285+04			4										
SUB-TOTALS			513	194	804	74	1497	224	26	92.4	10	24	24	124	219
TOTALS			3082					224	26	93	34		24	124	219

EROSION CONTROL SCHEDULE

LOCATION STA	TO	Sta	TEMP. EROSION. CONTROL. SEEDING (lb)	SEEDING CL 2 (ac)	NITROGEN FERTILIZER NUTRIENT (lb)	PHOSPHORUS FERTILIZER NUTRIENT (lb)	POTASSIUM FERTILIZER NUTRIENT (lb)	MULCH METHOD 2 (ac)
276+15	TO	276+50	1.06	0.01	0.21	0.21	0.21	0.01
276+50	TO	277+00	1.13	0.01	0.23	0.23	0.23	0.01
277+00	TO	277+50	1.90	0.01	0.38	0.38	0.38	0.01
277+50	TO	278+00	2.00	0.01	0.40	0.40	0.40	0.01
278+00	TO	278+50	0.71	0.01	0.14	0.14	0.14	0.01
278+50	TO	279+00	0.69	0.01	0.14	0.14	0.14	0.01
279+00	TO	279+50	0.54	0.01	0.11	0.11	0.11	0.01
279+50	TO	280+00	0.37	0.01	0.07	0.07	0.07	0.01
280+00	TO	280+50	0.43	0.01	0.09	0.09	0.09	0.01
280+50	TO	281+00	0.49	0.01	0.10	0.10	0.10	0.01
		TOTAL =	10	0.10	2*	2*	2*	0.10

* SEE GENERAL NOTE #19 ON SHEET NO. 2

EARTHWORK SCHEDULE

LOCATION STA	TO	STA	UNADJUSTED EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSED FOR 25% SHINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
276+15.58	TO	276+50.00	0.0	0.0	0.3	-0.3
276+50.00	TO	277+00.00	1.9	1.4	0.4	1.0
277+00.00	TO	277+50.00	6.6	5.0	0.0	5.0
277+50.00	TO	278+00.00	16.4	12.3	0.0	12.3
278+00.00	TO	278+50.00	23.2	17.4	0.1	17.3
278+50.00	TO	279+00.00	26.3	19.7	0.2	19.5
279+00.00	TO	279+50.00	32.3	24.2	0.1	24.1
279+50.00	TO	280+00.00	36.6	27.5	0.0	27.5
280+00.00	TO	280+50.00	38.4	28.8	0.0	28.8
280+50.00	TO	281+00.00	36.7	27.5	0.1	27.4
281+00.00	TO	281+30.00	12.7	9.5	0.0	9.5
		SUB-TOTAL	232	174	2	173

△1 Rev. 4-11-06

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

FAP ROUTE 592
SECTION 121I-1
ST. CLAIR COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 3/14/2006
FILE NAME = c:\pw_pcts\ec097705\plan\d97705c.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = REF