

LEGEND:

- 1 EXISTING GRADE
- (1A) EXISTING PATH
- PROPOSED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIXTURE C, N50 , 2"
- 3) PROPOSED AGGREGATE BASE COURSE TYPE B, 8"
- 4) PROPOSED TOPSOIL EXCAVATION AND PLACEMENT, 4"
- 5 PROPOSED HYDRO SEEDING W/MULCH, METHOD 2
- 6 PROPOSED THERMOPLASTIC PAVEMENT MARKING-LINE 4"
- 7 PROPOSED WOOD CHIPS 6"
- 8 REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL
- 9 PROPOSED POROUS GRANULAR EMBANKMENT, SUBGRADE





EXISTING AND PROPOSED BIKE PATH TYPICAL CROSS SECTION

STA. 10+00 TO STA. 45+40.09 STA. 63+52.52 TO STA. 74+38.38 STA. 80+36.26 TO STA. 82+55.80 STA. 90+00 TO STA. 91+30.87 STA. 95+00 TO STA. 96+59.25

EXISTING AND PROPOSED WALKING PATH TYPICAL CROSS SECTION

STA. 100+00 TO STA. 111+39.86 STA. 120+00 TO STA. 131+70.99 STA. 140+00 TO STA. 144+09.66 STA. 150+00 TO STA. 151+42.62 STA. 160+00 TO STA. 160+62.72 STA. 170+00 TO STA. 172+12.17

POROUS GRANULAR EMBANKMENT SUBGRADE (PGES) HAS BEEN PROVIDED AT THE LOCATIONS INDICATED FOR SOILS WHICH TEND TO BE UNSTABLE WHEN WET. ACTUAL NEED FOR REMOVAL AND REPLACEMENT WITH PGE WILL BE DETERMINED IN THE FIELD AT THE TIME OF CONSTRUCTION BY THE ENGINEER (BY USE OF A COME PENETROMETER IN CONJUNCTION WITH THE IDOT SUBGRADE MANUAL). If UNSUITABLE SOILS ARE ENCOUNTERED HE SOILS SHALL BE REMOVED AND REPLACED WITH PGE AND GROUND FABRIC FOR GROUND STABILIZATION. IF UNSUITABLE SOILS ARE NOT CONTROLLED WITH PGE AND GROUND FABRIC FOR GROUND STABILIZATION. IF UNSUABLE SOILS ARE NOT ENCOUNTERED, THEN THE QUANTITY WILL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE DUE TO THE CONTRACTOR.

BITUMINOUS MIXTURE REQUIREMENTS			
ITEM	AC-TYPE	VOIDS	RAP %
BITUMINOUS CONCRETE SURFACE COURSE,			
SUPERPAVE, MIXTURE C. N50	PG 64-22	4% € 50 G YR	15

ΉE	UNIT	WEIGHT	USE	ΤO	CAL	CUL.	TE .	ALL	BITUMIN	0115
URF	ACE I	MIXTURE	AUD	NTIT	IES	IS	112	LBS	S/SY/IN.	

REVISIONS NAME STRUCTURE REVISIONS	DATE 7/5/02	ILLINOIS DEPARTMENT O	F TRANSPORTATION
		TYPICAL SE	CTIONS
		SCALE: VERT. N.T.S. HORIZ, N.T.S. DATE 2/1/2006	DRAWN BY JOC CHECKED BY LMF

COUNTY TOTAL SHEETS

CONTRACT NO. 83532

TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT

SECTION -- 00-P4003-00-BT WILL

STA.