April 18, 2006

SUBJECT: FAU 306 (LaPorte Road)

Project M-8003(200)

Section 01-00029-00-FP (Mokena)

Will County

Contract No. 83825

Item 97

April 28, 2006 Letting

Addendum (A)

## TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Added special provision "Connect to Existing Manhole", revised special provision "Sanitary Sewer, PVC (D3034) SDR 26, 8".

## Plans - Revised plan sheet 55

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine

Engineer of Design and Environment

By: Ted B. Walschleger

Engineer of Project Development

Tet Delukyon DE.

and Implementation

LaPorte Road Reconstruction Wolf Road to Kirkstone Way Village of Mokena Local Agency Section 01-00029-00-FP

Manhole steps shall be Neenah Foundry Company R-1981-I or an Engineer approved equivalent. For field installation manhole steps shall be Neenah Foundry Company R-1981-S or an Engineer approved equivalent.

A performed and trowelable bituminous joint sealant shall be between adjusting rings and cone sections and at all barrel section joints. The preformed bituminous joint sealant shall be Kent-Seal, Ram-Nek, E-Z Stick or an Engineer approved equivalent. The minimum dimensions of the preformed material shall be ½-inch square. All manholes shall be inspected and leakage tested in accordance with ASTM C1244-93 or C969-94. This work shall be included in the price of the manhole.

Sanitary service connections to 5' diameter manholes shall be made with an internal drop connection as indicated in the plan details.

This item shall be paid for at the contract unit price per each for SANITARY MANHOLE, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID; or SANITARY MANHOLE, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID WITH INTERIOR DROP CONNECTION, which price shall include all labor, materials and equipment required to complete the work as described above, including the chimney seal, Class SI concrete, frame and lid, steps, preformed bituminous joint sealant, and pipe and anchors associated with the interior drop connection.

## CONNECT TO EXISTING MANHOLE

Added 4-18-06

This work shall include connecting proposed sanitary sewers to an existing sanitary manholes as indicated on the plans. New connections to existing manholes shall be angled in the direction of flow, and shall be accomplished by core drilling through the wall of the manhole and installing the appropriately sized connector boot, such as Kor-N-Seal by NPC, or approved equal.

This item shall be paid for at the contract unit price per each CONNECT TO EXISTING MANHOLE, which price shall include all labor, materials and equipment required to complete the work as described above, including the connector boot, labor to core drill the manhole and the action of inserting the sewer into the boot.

SANITARY SEWER, PVC (D3034) SDR 26, 8"

Revised 4-18-06

This work shall consist of furnishing and installing PVC sanitary sewer at the locations shown on the Plans or as directed by the Engineer. The work shall be done in accordance with Section 20, 30 and 31 of the Standard Specifications for Water and Sewer Main Construction in Illinois and the details shown on the Plans.