

SUMMARY OF QUANTITIES

ALGONQUIN RD. SIDEWALK IMPROVEMENTS		
HORIZ. SCALE: NONE	FILE NAME	2 OF 20
	SUMQUANT.DWG	SHEET NO.
SUMMARY OF QUANTITIES		
CONTRACT NO. 83836		

CODE NO.	ITEM	UNIT	QUANTITY	CONSTRUCTION TYPE CODE SFTY 1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	12	12
20200100	EARTH EXCAVATION	CY	215	215
21101625	TOPSOIL FURNISH AND PLACE, 6"	SY	2140	2140
25000400	NITROGEN FERTILIZER NUTRIENT	LB	40	40
25000500	PHOSPOROUS FERTILIZER NUTRIENT	LB	40	40
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	40	40
25200110	SODDING, SALT TOLERANT	SY	2140	2140
25200200	SUPPLEMENTAL WATERING	UNIT	3	3
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SY	1150	1150
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SF	9750	9750
42400800	DETECTABLE WARNINGS	SF	20	20
44000500	COMBINATION CURB AND GUTTER REMOVAL	FT	50	50
44213200	SAW CUTS	FT	65	65
60260100	INLETS TO BE ADJUSTED	EACH	8	8
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FT	350	350
67100100	MOBILIZATION	LUMP SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	LUMP SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	LUMP SUM	1	1
* 78000600	THERMOPLASTIC PAVEMENT MARKING LINE, 12"	FT	165	165
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FT	25	25
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 2/C	FT	405	405
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14, 3/C	FT	405	405
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT	EACH	2	2
* 87800100	CONCRETE FOUNDATION, TYPE A	FT	8	8
* 87900200	DRILL EXISTING HANDHOLE	EACH	2	2
* 88800100	PEDESTRIAN PUSH BUTTON	EACH	2	2
* 89502200	MODIFY EXISTING CONTROLLER	EACH	1	1
X2010505	CLEARING, SPECIAL	LUMP SUM	1	1
* X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED	EACH	6 6	6 6
Z0051500	REMOVING AND RESETTING STREET SIGNS	EACH	4	4
Z0077900	WOOD POST AND RAIL FENCE	FT	80	80
XX005314	BITUMINOUS DRIVEWAY REMOVAL	SY	20	20

* SPECIALTY ITEMS