

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	9
STA. 75+60.93		TO STA. 116+00.00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT # 84986				

← URBAN →

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07		4 - LANE 86+07 - 116+00		90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B
				100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A	100% STATE I000 - 2A			
A2000114	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
A2001714	TREE, ACER SACCHARUM (SUGAR MAPLE) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
A2003414	TREE, FRAXINUS AMERICANA AUTUMN BLAZE (AUTUMN BLAZE WHITE ASH) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
A2007114	TREE, QUERCUS RUBRA (RED OAK) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
A2007814	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD) 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15			15				
B2000562	TREE, AMELANCHIER CANADENSIS (SHADBLow SERVICEBERRY) 4' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	30			30				
B2001114	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	15			15				
B2002716	TREE, MALUS ADIRONDACK (ADIRONDACK CRABAPPLE) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10			10				
B2004814	TREE, MALUS SARGENTII (SARGENT CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	20			20				
B2005214	TREE, MALUS SUTYZAM (SUGAR TYME CRABAPPLE) 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	20			20				
C2012848	SHRUB, VIBURNUM TRILOBUM (AMERICAN CRANBERRY VIBURNUM) 4' HEIGHT, BALLED AND BURLAPPED	EACH	100			100				
X0321760	DOUBLE HANDHOLE REMOVAL	EACH	1				1			
X0321809	PERMANENT GROUND ANCHORS	EACH	32			32				
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	1946	55		1891				
X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	505			505				
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	708			708				
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 1C (GREEN)	FOOT	650				650			
X0323230	ISLAND SPECIAL	SQ YD	54			54				
X0323481	VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERA	EACH	1				1			
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	10892	7938		2954				
X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	12389	9506		2883				
X0324887	CONDUIT INSTALLED, 2 1/2" NON-METALLIC	FOOT	89				89			
X0324888	CONDUIT INSTALLED, 4" NON-METALLIC	FOOT	387				387			
X0712400	TEMPORARY PAVEMENT	SQ YD	4932	1343		3589				
X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	268			268				
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	210			210				
X4080020	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N50	TON	463	108		355				
X5011100	FOUNDATION REMOVAL	EACH	1	1						
X5121800	PERMANENT STEEL SHEET PILING	SQ FT	2028			2028				
X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3 SECTION, MAST ARM MOUNTED	EACH	7				7			
X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5 SECTION, BRACKET MOUNTED	EACH	3				3			
X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5 SECTION, MAST ARM MOUNTED	EACH	3				3			
X8810395	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE LED, 1-FACE, BRACKET MOUNTED	EACH	3				3			
X8810495	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE LED, 2-FACE, BRACKET MOUNTED	EACH	1				1			
X8880010	ADA PEDESTRIAN PUSHBUTTON	EACH	5				5			
XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND	1882					1882		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
X4074154	POLYMERIZED BITUMINOUS CONCRETE PAVEMENT, (FULL-DEPTH), SUPERPAVE, 13"	SQ YD	26453	5641		20812				
X0325312	POLYMERIZED BITUMINOUS CONCRETE PAVEMENT, (FULL-DEPTH), SUPERPAVE, 9 1/2"	SQ YD	2341			2341				
X0325313	CONDUIT INSTALLED, 2" NON-METALLIC	FOOT	95				95			

* SPECIALTY ITEM

SUMMARY OF QUANTITIES