

63500105	DELINEATORS	EACH
F.A. 595		
79+78	LT (BGN TRAF BAR TERM T2)	1
81+81	LT (END TRAF BAR TERM T1)	1
93+59	LT (CULV END SEC)	1
93+10	LT (CULV END SEC)	1
94+53	LT (CULV END SEC)	1
97+88	RT (CULV END SEC)	1
99+96	LT (CULV END SEC)	1
100+00	RT (CULV END SEC)	1
100+20	LT (CULV END SEC)	1
100+71	LT (CULV END SEC)	1
101+50	LT & RT (CULV END SEC)	4
102+00	LT & RT (CULV END SEC)	2
103+50	RT (CULV END SEC)	1
TOTAL		17

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	19
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT # 84986				

70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT
F.A. 595		
STG IIA / II	83+00 TO 87+56 1-WHITE	456
STG IIA / II	115+20 TO 119+50 1-WHITE	430
STG IIIA	85+40 TO 93+00 2-YELLOW	1520
STG IV	85+00 TO 86+00 1-YELLOW	100
STG IV - LEFT	116+00 TO 121+40 1-YELLOW	540
TOTAL		3,046

72000200	SIGN PANEL TYPE 2	SO FT
30TH STREET		
MAST ARM MOUNTED STREET SIGNS (BLACKHAWK ROAD)		19.50
TOTAL		19.50

78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT
F.A. 595		
74+47 TO 75+66	MEDIAN SOLID YELLOW	480
76+20 TO 78+72	MEDIAN DBL SOLID YELLOW	504
78+36 TO 95+32	LEFT DASH WHITE LANE	430
78+72 TO 81+43	MEDIAN DBL SOLID YELLOW X2	1512
81+43 TO 92+97	MEDIAN SOLID YELLOW X2	2094
81+43 TO 92+97	MEDIAN DASH YELLOW X2	540
91+61 TO 95+32	RIGHT DASH WHITE LANE	100
92+97 TO 95+32	MEDIAN DBL SOLID YELLOW	470
96+64 TO 99+42	MEDIAN DBL SOLID YELLOW	556
96+64 TO 122+00	LT / RT DASH WHITE LANE X2	1280
99+42 TO 122+00	MEDIAN SOLID YELLOW X2	4516
99+42 TO 120+50	MEDIAN DASH YELLOW X2	1060
INDIAN HILL ROAD		
10+48 TO 14+00	CL DBL SOLID YELLOW	704
30TH STREET		
298+10 TO 299+20	CL SOLID YELLOW	110
298+30 TO 298+80	CL DASH YELLOW	20
299+20 TO 299+45	CL DBL SOLID YELLOW	50
300+60 TO 304+00	CL DBL SOLID YELLOW	680
TOTAL		15,106

TRAFFIC CONTROL AND PROTECTION							
	70100500	70100200	70100400	70102620	70102622	70102632	
	STANDARDS	STANDARD	STANDARD	STANDARD	STANDARD	STANDARD	STANDARD
	701001/701006	701326	701331	701431	701501	701502	701602
	NOT MEAS	LUMP SUM	EACH	EACH	LUMP SUM	LUMP SUM	LUMP SUM
F.A. 595							
STG I	X / X	1					
STG IIA/II				1			
STG IIB/II				1			
STG IIIA/III					1		
STG IIIB/III		1		1			
STG IV							1
FINAL							1
30TH STREET							
STG I				1			
STG II - PH I		1					
STG II - PH II		1					
STG III - PH I		1					
STG III - PH II		1			1		
STG IV		1					
34TH STREET							
STG II - LEFT HALF				1			
STG II - RIGHT HALF				1			
TOTAL		1	4	4	1	1	1

70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT
F.A. 595		
STG IIA	75+61 TO 76+45 1-WHITE SKIP DASH	22
STG IIA	74+50 TO 76+80 1-WHITE SKIP DASH	58
STG IIB	74+50 TO 78+60 1-WHITE SKIP DASH	102
STG IIIA	74+50 TO 75+60 1-WHITE SKIP DASH	28
TOTAL		210

73000100	WOOD SIGN SUPPORT	FOOT
F.A. 595		
LEFT	STA 80+40	15
LEFT	STA 85+40	17
LEFT	STA 90+40	17
TOTAL		49

STD SPEC SEC 730.04(a) SHALL BE USED FOR INSTALLATION

70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT
F.A. 595		
STG IIB REMOVE STG IIA TAPERS		
74+50 TO 76+80	WB LT, RT AND SKIP DASH	155
STG IIB REMOVE STG IIA MARKINGS		
83+50 TO 87+56	EB RT EDGE, CL DBL, WB RT EDGE	348
STG IIIA REMOVE STG IIB MARKINGS		
63+70 TO 77+80	EB RT EDGE, WB DBL AND SKIP DASH	700
85+50 TO 91+00	CL - DBL YELLOW, EB RT EDGE	283
STG IIIB REMOVE STG IIIA MARKINGS		
74+50 TO 75+60	WB TAPER, SKIP DASH	50
75+60 TO 82+75	WB LT SINGLE, DBL	370
STG III REMOVE STG II MARKINGS		
116+00 TO 132+20	EB RT, EB LT, WB RT, WB LT	1067
STG IV REMOVE STG IIIB / III MARKINGS		
79+30 TO 86+50	WB RT	240
116+00 TO 132+20	EB LT, WB LT, WB RT	1260
STG III STOP BARS		
110		110
STG IV REMOVE STG IV MARKINGS		
75+60 TO 121+40	EB LT, WB LT, WB RT	3900
76+80 TO 85+00	WB RT SKIP DASH	102
30TH STREET		
STG II PH II REMOVE STG II PH I MARKINGS		
300+35 TO 304+00	NB RT, NB LT, SB LT AND STOP BARS	355
STG III PH I REMOVE STG II PH II MARKINGS		
298+10 TO 300+00	NB LT, SB LT, SB RT	187
300+70 TO 304+00	SB LT, SB RT, STOP BAR	155
STG III PH II REMOVE STG III PH I MARKINGS		
298+10 TO 299+55	NB / SB DBL, STOP BAR	119
301+79 TO 304+00	NB LT, SB LT	131
STG III PH II REMOVE STG III PH II MARKINGS		
297+25 TO 299+45	NB LT, SB LT, STOP BAR	154
300+10 TO 304+00	NB LT, SB LT, STOP BAR	287
TOTAL		9,973

78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT
F.A. 595		
75+08	25' LT RT TURN ARROW	15.6
75+50	25' LT WORD "ONLY"	20.8
75+85	25' LT RT TURN ARROW	15.6
76+25	25' LT WORD "ONLY"	20.8
76+60	25' LT RT TURN ARROW	15.6
76+60	0' LT LT TURN ARROW	15.6
77+60	0' LT LT TURN ARROW	15.6
78+60	0' LT LT TURN ARROW	15.6
82+80	0' LT LT TURN ARROW X2	31.2
85+30	0' LT LT TURN ARROW X2	31.2
87+80	0' LT LT TURN ARROW X2	31.2
90+30	0' LT LT TURN ARROW X2	31.2
92+80	0' LT LT TURN ARROW X2	31.2
93+67	0' LT LT TURN ARROW	15.6
94+40	0' LT LT TURN ARROW	15.6
95+12	0' LT LT TURN ARROW	15.6
94+44	37' RT RT TURN ARROW	15.6
95+12	37' RT RT TURN ARROW	15.6
97+07	0' LT LT TURN ARROW	15.6
97+90	0' LT LT TURN ARROW	15.6
98+72	0' LT LT TURN ARROW	15.6
97+07	37' LT RT TURN ARROW	15.6
97+90	37' LT RT TURN ARROW	15.6
98+72	37' LT RT TURN ARROW	15.6
100+00	0' LT LT TURN ARROW X2	31.2
102+50	0' LT LT TURN ARROW X2	31.2
105+00	0' LT LT TURN ARROW X2	31.2
108+00	0' LT LT TURN ARROW X2	31.2
111+00	0' LT LT TURN ARROW X2	31.2
113+50	0' LT LT TURN ARROW X2	31.2
116+00	0' LT LT TURN ARROW X2	31.2
119+00	0' LT LT TURN ARROW X2	31.2
121+50	0' LT LT TURN ARROW	15.6
30TH STREET		
301+15	18' LT RT TURN ARROW	15.6
301+85	18' LT RT TURN ARROW	15.6
302+55	18' LT RT TURN ARROW	15.6
TOTAL		774.8

78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT
F.A. 595		
74+54 TO 76+89	LEFT SOLID WHITE LANE	235
76+20 TO 78+72	LEFT SOLID WHITE LANE	252
76+89 TO 79+85	LEFT SKIP DASH WHITE	74
78+72 TO 80+16	LEFT SKIP DASH WHITE	40
93+47 TO 95+56	MEDIAN SOLID WHITE LANE	209
94+37 TO 95+71	RIGHT SOLID WHITE LANE	134
95+56 RT CORNER ISLAND	SOLID WHITE LANE	97
95+80 LT CORNER ISLAND	SOLID WHITE LANE	88
96+50 LT CORNER ISLAND	SOLID WHITE LANE	123
96+44 TO 98+92	LEFT SOLID WHITE LANE	248
96+44 TO 98+92	MEDIAN SOLID WHITE LANE	248
95+60 RT TO 95+76 LT	CROSSWALK	128
121+00 TO 122+00	MEDIAN SOLID WHITE LANE	100
INDIAN HILL ROAD		
10+36 TO 10+44	CROSSWALK	94
30TH STREET		
300+43 TO 302+63	LEFT SOLID WHITE LANE	220
SW QUADRANT	CROSS WALK	36
NW QUADRANT	CROSS WALK	72
NE QUADRANT	CROSS WALK	58
BETWEEN ISLANDS	CROSS WALK	74
TOTAL		2,530

70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT
F.A. 595		
STG IIA/II	74+50 TO 132+20 (STD 701431 1-WHITE, 2-YELLOW = 14955')	3514
	74+50 TO 119+50 WB RT EDGE WHITE	
STG IIB	63+70 TO 87+56 (STD 701431 1-WHITE, 2-YELLOW = 4998')	
STG IIB	82+75 TO 87+56 WB RT EDGE WHITE	481
STG IIIA	74+50 TO 93+00 EB LT EDGE, WB LT EDGE	2940
STG III	93+00 TO 132+20 (STD 701431 1-WHITE, 2-YELLOW = 10380')	
STG IIIB	74+50 TO 93+00 (STD 701431 1-WHITE, 2-YELLOW = 5070')	
STG IIIB	74+50 TO 77+00 WB LT EDGE AND DASHED LANE	300
STG IV	75+61 TO 116+00 EB LT EDGE, WB LT EDGE	7800
30TH STREET		
ALL PHASES	298+10 TO 304+00 (STD 701331 2-WHITE, 2-YELLOW = 6320')	
TOTAL		15,035

72000100	SIGN PANEL TYPE 1	SO FT
F.A. 595		
LEFT	STA 80+40	6.25
LEFT	STA 85+40	9.00
LEFT	STA 90+40	9.00
	MAST ARM MOUNTED STREET SIGNS (30TH ST)	15.00
TOTAL		39.25

SIGN PANEL SHALL BE 0.125 INCHES THICK

ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-001533



Stanley Consultants Inc.
850 West Higgins Road, Suite 730, Chicago, Illinois 60639-2801
www.stanleygroup.com

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A. 595 (IL RTE 5)

SCALE: VERT. NONE
HORIZ. DATE 15-FEB-2006

DRAWN BY XX
CHECKED BY XX