

SCHEDULE OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT # 84986				

87800100	CONCRETE FOUNDATION, TYPE A	FOOT
F.A. 595		
	96+75.0 LT 68.0' (POST 1)	3.0
	95+76.0 LT 35.5' (POST 3)	3.0
TOTAL		6.0

87800200	CONCRETE FOUNDATION, TYPE D	FOOT
F.A. 595		
	96+75 LT	3.5
TOTAL		3.5

87800415	CONCRETE FOUNDATION, TYPE E 36 INCH DIAMETER	FOOT
F.A. 595		
	95+34.9 RT 68.6' (POLE 3)	13.0
	96+62.1 LT 73.6' (POLE 1)	13.0
	95+32.0 LT 52.5' (POLE 2)	15.0
	96+50.2 RT 45.5' (POLE 4)	15.0
TOTAL		56.0

88200400	TRAFFIC SIGNAL BACKPLATE, FORMED PLASTIC	EACH
F.A. 595		
	SIGNAL HEADS 2, 3, 4, 5, 6, 8, 9, 10, 11, AND 12.	10
TOTAL		10

89000200	TEMPORARY TRAFFIC SIGNAL INSTALLATION	L SUM
F.A. 595		
	30TH STREET INTERSECTION	1
TOTAL		1

89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH
F.A. 595		
	30TH STREET INTERSECTION	1
TOTAL		1

89502380	REMOVE EXISTING HANDHOLE	EACH
F.A. 595		
	92+13 RT 27'	1
	93+80 RT 30'	1
	95+27 RT 25'	1
	95+85 LT 25'	1
	96+16 RT 30'	1
	96+25 LT 25'	1
	97+84 LT 35'	1
	99+27 LT 32'	1
TOTAL		8

89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH
F.A. 595		
	95+40 LT 35'	1
	95+55 RT 42'	1
	96+22 RT 30'	1
	96+56 LT 58'	1
	96+75 LT 73'	1
TOTAL		5

X0321760	DOUBLE HANDHOLE REMOVAL	EACH
F.A. 595		
	96+70 LT 67'	1
TOTAL		1

X0322923	SEGMENTAL CONCRETE BLOCK WALL	SO FT
F.A. 595		
	106+95, 60' RT TO 107+10, 43.58' RT	315
	108+58, 43.58' RT TO 108+79, 75' RT	168
34TH STREET		
	18+61.1 TO 19+01.1 20' LT	225
TOTAL		708

X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, NO. 6 IC (GREEN)	FOOT
F.A. 595		
	POLE 1 TO HH 1	16
	POST 1 TO HH 1	8
	POLE 2 TO HH 2	16
	POST 2 TO HH 2	16
	POST 3 TO HH 2	58
	POLE 3 TO HH 3	8
	POLE 4 TO HH 4	16
	HH 1 TO HH 2	144
	HH 1 TO HH 4	121
	HH 3 TO HH 4	136
	HH 1 TO CONTROLLER	10
	CONTROLLER TO SERVICE	101
TOTAL		650

X0323230	ISLAND SPECIAL	SO YD
F.A. 595		
30TH STREET		
	LEFT NW QUAD ISLAND	30
	RIGHT NE QUAD ISLAND	24
TOTAL		54

X0323481	VIDEO VEHICLE DETECTION SYSTEM, 4 CAMERAS	EACH
F.A. 595		
	30TH STREET INTERSECTION	1
TOTAL		1

X0324887	CONDUIT, INSTALLED, 2 1/2" NON-METALIC	FOOT
F.A. 595		
	POLE 1 TO HH 1	6
	POLE 2 TO HH 2	10
	POLE 3 TO HH 3	3
	POLE 4 TO HH 4	11
	POST 3 TO HH 2	50
	POST 2 TO HH 2	8
	POST 1 TO HH 1	1
TOTAL		89

X0324888	CONDUIT, INSTALLED, 4" NON-METALIC	FOOT
F.A. 595		
	HH 1 TO CONTROLLER	8
	HH 2 TO HH 1	138
	HH 4 TO HH 1	111
	HH 4 TO HH 3	130
TOTAL		387

X2510630	HEAVY DUTY EROSION CONTROL BLANKET	SO YD
F.A. 595		
	STA 93+05 TO STA 93+65 LT	67
	STA 94+40 TO STA 94+55 LT	17
	STA 101+35 TO STA 101+60 LT	53
	STA 103+25 TO STA 103+90 RT	72
	STA 105+10 TO STA 105+35 LT	17
	STA 111+17 LT (END RET WALL A)	6
	STA 112+55 LT (END RET WALL A)	36
TOTAL		268

X5011100	FOUNDATION REMOVAL	EACH
F.A. 595		
	STA 82+35, 60' RT	1
TOTAL		1

X8801310	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3 SECTION, MAST ARM MOUNTED	EACH
F.A. 595		
	SIGNAL HEADS 2, 3, 4, 5, 8, 10, AND 11	7
TOTAL		7

X8801395	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5 SECTION, BRACKET MOUNTED	EACH
F.A. 595		
	SIGNAL HEADS 1, 7 AND 13	3
TOTAL		3

X8801400	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5 SECTION, MAST ARM MOUNTED	EACH
F.A. 595		
	SIGNAL HEADS 6, 9, AND 12	3
TOTAL		3

X8810395	PEDESTRIAN SIGNAL HEAD POLYCARBONATE, LED, 1 FACE, BRACKET MOUNTED	EACH
F.A. 595		
	POST 1	1
	POLE 2	1
	POLE 3	1
TOTAL		3

X8810495	PEDESTRIAN SIGNAL HEAD POLYCARBONATE, LED, 2 FACE, BRACKET MOUNTED	EACH
F.A. 595		
	POST 3	1
TOTAL		1

X88800100	ADA PEDESTRIAN PUSHBUTTON	EACH
F.A. 595		
	POLE 1	1
	POST 2	1
	POST 3	2
	POLE 3	1
TOTAL		5

XX003037	DUCTILE IRON FITTINGS AND ACCESSORIES	POUND
STA 105+17	10" PIPE CAP	35
	10" 90 ELBOW	190
	10" X 10" X 6" TEE	250
STA 109+ 05	10" X 10" X 6" TEE	250
STA 109+ 75	10" X 10" X 6" TEE	250
	6" 45 ELBOW	75
	6" WYE	125
	6" PIPE CAP	17
STA 112+ 50	10" 45 ELBOW X2	155
STA 115+ 85	10" PIPE CAP	35
	10" 90 ELBOW	190
	10" TEE	310
TOTAL		1,882

*2001377	CONDUIT, INSTALLED, 2" NON-METALIC	FOOT
F.A. 595		
	SERVICE TO CONTROLLER	95
TOTAL		95

REVISIONS	
NAME	DATE

ILLINOIS PROFESSIONAL
DESIGN FIRM NO. 184-001533



Stanley Consultants Inc.
858 West Higgins Road, Suite 130, Chicago, Illinois 60639-2803
www.stanleygroup.com

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES F.A. 595 (IL RTE 5)

SCALE: VERT. NONE
HORIZ. NONE
DATE 15-FEB-2006

DRAWN BY XX
CHECKED BY XX