

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
04-00137-03-FP		HENRY	31	6
F.L.A. 224		ILLINOIS		FED. AID PROJECT BR-084707
FED. ROAD DIST. NO. 7				

SCHEDULES

EROSION CONTROL BLANKET		
STATION	S.Y.	REMARKS
Wolf Rd.		
L 688+00 - 41+50	77	6' WIDE
L 689+50 - 693+69	279	6' WIDE
1280 E. Rd.		
R 41+02 - L 689+50	74	6' WIDE
R 41+52 - 42+00	32	6' WIDE
PROJECT TOTAL	462	

25100630

TEMPORARY DITCH CHECK		
STATION	EACH	REMARKS
Wolf Rd.		
L & R 678+50	2	AS DIRECTED BY THE ENGINEER
L 680+50	2	AS DIRECTED BY THE ENGINEER
L & R 683+50	1	AS DIRECTED BY THE ENGINEER
L 686+00	1	AS DIRECTED BY THE ENGINEER
L 688+00	1	AS DIRECTED BY THE ENGINEER
R 690+00	2	AS DIRECTED BY THE ENGINEER
L 693+50	1	AS DIRECTED BY THE ENGINEER
L & R 698+50	2	AS DIRECTED BY THE ENGINEER
1280 E. Rd.		
L & R 42+00	2	AS DIRECTED BY THE ENGINEER
PROJECT TOTAL	14	

28000300

PERIMETER EROSION BARRIER		
STATION	FOOT	REMARKS
R 691+50 - 696+00	450	SET OUT INSIDE OF R.O.W. LINE
R 697+50 - 699+00	150	SET OUT INSIDE OF R.O.W. LINE
PROJECT TOTAL	600	

28000400

SUB-BASE GRANULAR MATERIAL, TYPE B		
STATION	TONS	REMARKS
Wolf Rd.		
L 678+10.84 - 688+50.05	313	8"
L 689+10.02 - 698+64.17	543	8"
R 678+10.84 - 688+64.29	290	8"
R 688+64.29 - 698+64.17	273	8"
1280 E. Road		
L 40+19 - 42+02	59	8"
R 40+19 - 42+02	83	8"
STA. 40+20 - 40+31	39	15" PIPE REMOVAL - 1' +/-
PROJECT TOTAL	1,600	

31101000

AGGREGATE BASE COURSE, TYPE A		
STATION	TONS	REMARKS
Wolf Rd.		
L 678+10.84 - 688+50.05	156	4
PER 682+63	170	8
CER 686+31	31	8
L 689+10.02 - 698+64.17	271	4
R 678+10.84 - 688+64.29	145	4
R 688+64.29 - 698+64.17	137	4
PER 690+48	13	8
FEL 693+88.5	18	10
1280 E. Road		
L 40+19 - 42+02	29	4
R 40+19 - 42+02	41	4
STA. 40+20 - 40+31	13	15" PIPE REMOVAL - 4"
PER 41+32	21	8
PROJECT TOTAL	1,050	

35100100

AGGREGATE SURFACE COURSE, TYPE B		
STATION	TONS	REMARKS
AS NEEDED BY ENGR.		
	30	CONTINGENCY ITEM FOR TEMP. ENTR'S.
PROJECT TOTAL	30	

40200800

BITUMINOUS MATERIALS (PRIME COAT)		
STATION	GALLONS	REMARKS
L & R 678+10.84 - 698+64.17	1,694	.5 GAL S.Y.
L & R 40+19 - 42+03	8	.5 GAL S.Y.
CONTINGENCY		
L & R 678+10.84 - 698+64.17	891	.1 GAL S.Y.
L & R 40+19 - 42+03	47	.1 GAL S.Y.
PROJECT TOTAL	2,863	

40600100

AGGREGATE PRIME COAT		
STATION	TONS	REMARKS
ENTIRE PROJECT		
	14	3 LBS S.Y.
PROJECT TOTAL	14	

40600300

BITUMINOUS BASE COURSE SUPERPAVE		
STATION	TONS	REMARKS
Wolf Rd.		
L 678+10.84 - 688+50.05	185	4 1/2"
L 689+10.02 - 698+64.17	322	4 1/2"
R 678+10.84 - 688+50.05	172	4 1/2"
R 689+10.02 - 698+64.17	162	4 1/2"
1280 E. Road		
L 40+19 - 42+02	35	4 1/2"
R 40+19 - 42+02	49	4 1/2"
STA. 40+20 - 40+31	15	15" PIPE REMOVAL
PROJECT TOTAL	918	

X3550010

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50		
STATION	TONS	REMARKS
Wolf Rd.		
L 678+10.84 - 688+64.29	220	1 1/2" PLUS LEVELING, 1.75", 1 LIFT
R 678+10.84 - 688+64.29	216	1 1/2" PLUS LEVELING, 1.75", 1 LIFT
PER 682+63	67	3"
CER 686+31	10	3"
L 688+64.29 - 698+64.17	271	1 1/2" PLUS LEVELING, 1.75", 1 LIFT
R 688+64.29 - 698+64.17	205	1 1/2" PLUS LEVELING, 1.75", 1 LIFT
PER 690+48	5	3"
1280 E. Rd.		
L & R 40+19 - 42+03	81	1 1/2" PLUS LEVELING, 1.75", 1 LIFT
PER 41+32	8	3"
PROJECT TOTAL	1,087	

X4066414

BITUMINOUS SURFACE REMOVAL - BUTT JOINT		
STATION	SQ YD	REMARKS
Wolf Rd.		
678+10.84 - 678+35.84	67	
698+39.17 - 698+64.17	67	
1280 E. Rd.		
41+78 - 42+03	67	
PROJECT TOTAL	201	

40600980