

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
224	04-00137-03-FP	HENRY	31	7
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT SP-224(107)	

SCHEDULES

PORTLAND CEMENT CONCRETE DRIVEWAY, 7"		
STATION	SQ YD	REMARKS
RT. 682+75	8	
PROJECT TOTAL	8	

42300300

STRIP REFLECTIVE CRACK CONTROL TREATMENT		
STATION	FOOT	REMARKS
Wolf Rd.		
L 678+60.84 - 687+38.21	877	2' WIDE APPLIED ALONG WIDENING
L 689+34.01 - 698+14.17	880	2' WIDE APPLIED ALONG WIDENING
R 678+60.84 - 698+14.17	1,953	2' WIDE APPLIED ALONG WIDENING
1280 E. Rd.		
L 40+19 - 42+03	284	2' WIDE APPLIED ALONG WIDENING
R 40+19 - 42+03	230	2' WIDE APPLIED ALONG WIDENING
PROJECT TOTAL	4,224	

44300200

BITUMINOUS SHOULDERS SUPERPAVE		
STATION	TON	REMARKS
Wolf Rd.		
L 678+10.84 - 688+29	347	7" COMPLETE
R 678+10.84 - 688+64.29	386	7" COMPLETE
R 688+64.29 - 698+64.17	360	7" COMPLETE
L 688+98 - 698+64.17	284	7" COMPLETE
1280 E. Rd.		
L 40+40 - 42+03	50	7" COMPLETE
R 40+55 - 42+03	38	7" COMPLETE
PROJECT TOTAL	1,465	

48202000

PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"		
STATION	EACH	REMARKS
Wolf Rd.		
R 682+00	1	
PROJECT TOTAL	1	

54213657

PIPE CULVERTS, CLASS D, TYPE 1 15"		
STATION	FOOT	REMARKS
Wolf Rd.		
PER 690+30 - 690+66	36	WOLF RD.
FEL 693+69 - 694+07	38	WOLF RD.
1280 E. Rd.		
PER 41+12 - 41+52	40	1280 EAST RD.
PROJECT TOTAL	114	

54200220

PIPE CULVERTS, CLASS D, TYPE 1 36"		
STATION	FOOT	REMARKS
Wolf Rd.		
R 697+84	6	PIPE CULVERT EXTENSION
PROJECT TOTAL	6	

54200241

STORM SEWERS, CLASS A, TYPE 1 12"		
STATION	FOOT	REMARKS
Wolf Rd.		
R 682+00 - 682+92	88	
PROJECT TOTAL	88	

550A0050

PIPE DRAINS, 10" SPECIAL		
STATION	FOOT	REMARKS
Wolf Rd.		
682+92 - 683+25	32	CONTINGENCY PLAN
683+25 - 686+12	287	CONTINGENCY PLAN
PROJECT TOTAL	319	

60101905

CONCRETE GUTTER, TYPE A (MODIFIED)		
STATION	FOOT	REMARKS
RT. 682+73 - RT. 683+37.5	96	
RT. 683+37.5 - RT. 686+08	271	
PROJECT TOTAL	367	

60602600

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
Wolf Rd.		
678+10.84 - 698+64.17	376	4-40 CL MARKING - 2 LIFTS
1280 E. Rd.		
40+49 - 42+03	32	4-40 CL MARKING - 2 LIFTS
PROJECT TOTAL	408	

70300100

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS		
STATION	EACH	REMARKS
Wolf Rd.		
40' LT 679+50	1	
50' LT 679+50	1	
40' RT 682+00	1	
40' RT 683+15	1	
40' RT 687+33	1	
45' RT 687+33	1	
50' LT 687+80	1	
50' LT 689+50	1	
50' LT 694+48.70	1	
40.58' LT 694+8.8	1	
45' RT 698+00	1	
40' RT 698+00	1	
1280 East Rd.		
35.25' LT 41+00	1	
40' RT 41+00	1	
40' RT 41+50	1	
33' RT 41+50	1	
PROJECT TOTAL	16	

66600105

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
Wolf Rd.		
678+10.84 - 698+64.17	188	
1280 E. Rd.		
40+49 - 42+03	16	
PROJECT TOTAL	204	

70301000

SIGN PANEL - TYPE 1		
STATION	SQ FT	REMARKS
33' RT 686+52	6.25	R 3-2 (NO LEFT TURN) - 30" x 30"
PROJECT TOTAL	6.25	

72900100

METAL POST TYPE-A		
STATION	FOOT	REMARKS
33' RT 686+52	12	R 3-2 (NO LEFT TURN) - 30" x 30"
PROJECT TOTAL	12	

72900100