

# SCHEDULES

FILE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
89	D4-00229-00-FR	OGLE	42	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

REMOVE AND RE-ERECT RIGHT OF WAY MARKERS		
STATION	EACH	REMARKS
33' LT 11+20.69	1	
<b>PROJECT TOTAL</b>	<b>1</b>	

66600400

MOBILIZATION		
STATION	L SUM	REMARKS
ENTIRE PROJECT	1	
<b>PROJECT TOTAL</b>	<b>1</b>	

67100100

SHORT-TERM PAVEMENT MARKING		
STATION	FOOT	REMARKS
10+84 - 89+65	716	4-40 CL MARKING
KYTE ROAD	12	4-40 CL MARKING
<b>PROJECT TOTAL</b>	<b>728</b>	

70300100

WORK ZONE PAVEMENT MARKING REMOVAL		
STATION	SQ FT	REMARKS
10+84 - 89+65	239	4-40 CL MARKING
KYTE ROAD	4	4-40 CL MARKING
<b>PROJECT TOTAL</b>	<b>243</b>	

70301000

THERMOPLASTIC PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
L 10+84 - 63+40.72	5,287	WHITE EDGE LINE
R 10+84 - 63+40.72	5,298	WHITE EDGE LINE
L 63+40.72 - 89+65	2,675	WHITE EDGE LINE
R 63+40.72 - 84+51	2,138	WHITE EDGE LINE
R 84+51 - 89+65	532	WHITE EDGE LINE
<b>PROJECT TOTAL</b>	<b>15,930</b>	

78000200

THERMOPLASTIC PAVEMENT MARKING - LINE 24"		
STATION	FOOT	REMARKS
L 10+86	28	STOP LINE
R 89+54	20	STOP LINE
<b>PROJECT TOTAL</b>	<b>48</b>	

78000650

BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C" N50		
STATION	TON	REMARKS
10+84 - 63+40.72	1,295	1 1/2" - INCLUDING KYTE RD
63+40.72 - 89+65	653	1 1/2" - INCLUDING KYTE RD
PUBLIC ROAD - 84+51	10	1 1/2"
<b>PROJECT TOTAL</b>	<b>1,958</b>	

X4066414

BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, N50		
STATION	TON	REMARKS
10+84 - 63+40.72	1,295	1 1/2" - INCLUDING KYTE RD
63+40.72 - 89+65	653	1 1/2"
PUBLIC ROAD - 84+51	10	1 1/2"
<b>PROJECT TOTAL</b>	<b>1,958</b>	

XX005347

BREAKER-RUN CRUSHED STONE		
STATION	TON	REMARKS
CONTINGENCY ITEM	205	AS DIRECTED BY THE ENGINEER
<b>PROJECT TOTAL</b>	<b>205</b>	

Z0005400