

STORM SEWER REMOVAL SCHEDULE						
LOCATION	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 36"	REMOVING MANHOLES	REMOVING INLETS	CONCRETE HEADWALL REMOVAL SPECIAL
	FT	FT	FT	EA	EA	EA
LAFAYETTE AVENUE						
STA. 10+00.00 TO STA. 16+00.00	74.30		12.50			1
STA. 16+00.00 TO STA. 22+00.00	102.95	38.14		2		
STA. 22+00.00 TO STA. 28+00.00	51.42					
STA. 28+00.00 TO STA. 34+00.00	141.51	107.69		1	1	
STA. 34+00.00 TO STA. 34+86.00						
SANDRON AVE						
STA. 90+26.69 TO STA. 90+14.69	10.00					
SUBTOTAL	370.18	143.83	12.50	3	1	1
TOTAL	371	144	13	3	1	1

CURB AND GUTTER SCHEDULE			
LOCATION	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	CONCRETE GUTTER
	FOOT	FOOT	FOOT
LAFAYETTE AVENUE			
STA. 10+00.00 TO STA. 16+00.00			1130.00
STA. 16+00.00 TO STA. 22+00.00	72.00		1041.00
STA. 22+00.00 TO STA. 28+00.00	62.00		1074.00
STA. 28+00.00 TO STA. 34+00.00	54.00	95.52	950.00
STA. 34+00.00 TO STA. 34+86.00			86.00
SANDRON AVENUE			
STA. 90+14.11 TO STA. 93+12.22			321.25
STA. 90+12.59 TO STA. 94+16.94			413.31
SUBTOTAL	188.40	830.08	4,281.00
TOTAL	188.5	830.5	4,281.0

FENCE REMOVAL SCHEDULE				
LOCATION	SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED	CHAIN LINK FENCE REMOVAL	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	REMOVE AND RESET ORNAMENTAL FENCE
	FT	FT	FT	FT
S. LAFAYETTE AVENUE				
STA. 14+86.69	22.50	LT	TO STA. 15+54.51	25.63
STA. 15+74.26	25.30	LT	TO STA. 15+81.38	21.32
STA. 17+15.82	54.27	RT	TO STA. 17+84.55	24.41
STA. 19+69.07	19.25	LT	TO STA. 19+69.11	23.77
STA. 25+12.06	21.23	RT	TO STA. 25+79.16	22.89
STA. 33+05.49	21.99	LT	TO STA. 33+20.27	22.16
SANDRON AVENUE				
STA. 92+27.99	1296.00	RT	TO STA. 92+59.34	13.68
SUBTOTAL	115.98		4.52	138.34
TOTAL	116		5	139

ENGINEER'S FIELD OFFICE SCHEDULE	
LOCATION	ENGINEER'S FIELD OFFICE, TYPE A
	CAL MO
ENTIRE PROJECT	10
SUBTOTAL	10
TOTAL	10

MOBILIZATION SCHEDULE	
LOCATION	MOBILIZATION
	L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION SCHEDULE	
LOCATION	TRAFFIC CONTROL AND PROTECTION
	L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

TRAFFIC CONTROL SURVEILLANCE SCHEDULE	
LOCATION	TRAFFIC CONTROL SURVEILLANCE
	CAL DA
ENTIRE PROJECT	100
SUBTOTAL	100
TOTAL	100

CONSTRUCTION LAYOUT SCHEDULE	
LOCATION	CONSTRUCTION LAYOUT
	L. SUM
ENTIRE PROJECT	1
SUBTOTAL	1
TOTAL	1

TRAINEES SCHEDULE	
LOCATION	TRAINEES
	HOUR
PROJECT SITE	500
SUBTOTAL	500
TOTAL	500

SANITARY SCHEDULE			
LOCATION	SANITARY MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	SANITARY SEWER SERVICE REMOVAL AND REPLACEMENT	
	EA	FT	
LAFAYETTE AVENUE			
STA. 13+11.61	1.58	LT	1
STA. 15+85.56	1.31	LT	1
STA. 13+90.00		LT	23
STA. 15+20.00		LT	23
STA. 16+99.58	0.16	RT	1
STA. 20+03.47	0.58	RT	1
STA. 16+20.00		LT	23
STA. 17+30.00		LT	25
STA. 18+40.00		LT	25
STA. 19+50.00		LT	25
STA. 19+90.00		LT	25
STA. 20+50.00		LT	25
STA. 21+05.00		LT	25
STA. 21+50.00		LT	25
STA. 23+19.76	3.60	RT	1
STA. 26+36.17	5.64	RT	1
STA. 22+40.00		LT	25
STA. 23+85.00		LT	25
STA. 24+70.00		LT	25
STA. 29+36.90	4.78	RT	1
STA. 30+09.06	3.60	RT	1
STA. 32+16.25	3.70	RT	1
STA. 34+49.09	4.57	RT	1
			0
SUBTOTAL	10		319
TOTAL	10		319

PERMANENT THERMOPLASTIC PAVEMENT MARKING SCHEDULE				
LOCATION	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	
	YELLOW	WHITE	WHITE	
	FT	FT	FT	
LAFAYETTE AVENUE				
STA. 10+00.00 TO STA. 16+00.00		325.4	69.0	
STA. 16+00.00 TO STA. 22+00.00		166.1	26.4	
STA. 22+00.00 TO STA. 28+00.00		150.1	24.1	
STA. 28+00.00 TO STA. 34+00.00		233.1	36.3	
STA. 34+00.00 TO STA. 34+86.00		0.0	0.0	
STA. 10+38.50 TO STA. 34+86.04	611.9			
RUSTY LANE				
STA. 60+00.00 TO STA. 61+56.17	34.0		12.0	
SANDRON AVENUE				
STA. 90+13.00 TO STA. 94+16.94	104.0		12.0	
SUBTOTAL	611.9	874.6	155.7	
TOTAL	612	875	156	

DETECTABLE WARNING SCHEDULE		
LOCATION	DETECTABLE WARNINGS	
	SQ FT	
LAFAYETTE AVENUE		
STA. 10+26	RT	6
STA. 10+26	LT	6
STA. 10+34	LT	6
STA. 10+34	RT	6
STA. 16+72	RT	6
STA. 17+25	RT	6
STA. 20+40	RT	6
STA. 20+97	RT	6
STA. 22+92	LT	6
STA. 23+46	LT	6
STA. 25+70	RT	6
STA. 26+20	RT	6
STA. 29+36	LT	6
STA. 29+85	RT	6
STA. 29+95	LT	6
STA. 30+39	RT	6
STA. 31+94	RT	6
STA. 32+40	RT	6
STA. 33+80	RT	6
TOTAL		114

TREE SCHEDULE	
LOCATION	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 2" CALIPER, BALLED AND BURLAPPED
	EACH
	8
SUBTOTAL	8
TOTAL	8

RETAINING WALL SCHEDULE		
LOCATION	MODULAR RETAINING WALL SYSTEM	
	SQ FT	
SANDRON AVENUE		
STA. 90+70.58 TO STA. 91+40.00	LT	410.00
STA. 92+60.00 TO STA. 93+10.71	LT	177.49
SUBTOTAL		587.5
TOTAL		588